



Notice of Application for a Planning Permit

The land affected by the application is located at:	L210 PS902144 V12580 F628 8 Monterey Way, Pakenham VIC 3810	
The application is for a permit to:	Buildings and Works (Construction of a Dwelling and a Fence)	
A permit is required under the following clauses of the planning scheme:		
42.01-2	Construct a building or construct or carry out works	
42.01-2	Construct a fence	
APPLICATION DETAILS		
The applicant for the permit is:	Frenken Homes Pty Ltd	
Application number:	T240636	
<p>You may look at the application and any documents that support the application at the office of the responsible authority:</p> <p>Cardinia Shire Council, 20 Siding Avenue, Officer 3809.</p> <p>This can be done during office hours and is free of charge.</p> <p>Documents can also be viewed on Council's website at cardinia.vic.gov.au/advertisedplans or by scanning the QR code.</p>		
HOW CAN I MAKE A SUBMISSION?		
<p>This application has not been decided. You can still make a submission before a decision has been made. The Responsible Authority will not decide on the application before:</p>		03 April 2025
<p>WHAT ARE MY OPTIONS?</p> <p>Any person who may be affected by the granting of the permit may object or make other submissions to the responsible authority.</p> <p>If you object, the Responsible Authority will notify you of the decision when it is issued.</p>	<p>An objection must:</p> <ul style="list-style-type: none"> • be made to the Responsible Authority in writing; • include the reasons for the objection; and • state how the objector would be affected. 	<p>The Responsible Authority must make a copy of every objection available at its office for any person to inspect during office hours free of charge until the end of the period during which an application may be made for review of a decision on the application.</p>



This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

Application Summary

Portal Reference A42461XR

Basic Information

Proposed Use	CONSTRUCTION OF A SINGLE STORY DWELLING WITH DOUBLE GARAGE ON LAND SUBJECT TO ENVIRONMENTAL SIGNIFICANCE OVERLAY
Current Use	VACANT
Cost of Works	\$265,510
Site Address	8 Monterey Way Pakenham 3810

Covenant Disclaimer

Does the proposal breach, in any way, an encumbrance on title such as restrictive covenant, section 173 agreement or other obligation such as an easement or building envelope? No such encumbrances are breached

Note: During the application process you may be required to provide more information in relation to any encumbrances.

Contacts

Type	Name	Address	Contact Details
Applicant	Hayley Woodall FRENKEN HOMES	194 Sladen street, Cranbourne VIC 3977	W: 03-5995-1655 E: info@frenkenhomes.com.au
Owner	[REDACTED]	[REDACTED]	
Preferred Contact	Hayley Woodall FRENKEN HOMES	194 Sladen street, Cranbourne VIC 3977	W: 03-5995-1655 E: info@frenkenhomes.com.au

Fees

Regulation Fee Condition	Amount	Modifier	Payable
9 - Class 4 More than \$100,000 but not more than \$500,000	\$1,420.70	100%	\$1,420.70
Total			\$1,420.70

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.



Civic Centre
20 Siding Avenue, Officer, Victoria

Council's Operations Centre (Depot)
Purton Road, Pakenham, Victoria

Postal Address
Cardinia Shire Council
P.O. Box 7, Pakenham VC, 3810

Email: mail@cardinia.vic.gov.au

Monday to Friday 8.30am–
5pm

Phone: 1300 787 624
After Hours: 1300 787 624
Fax: 03 5941 3784

Documents Uploaded

Date	Type	Filename
29-11-2024	Site plans	SITE PLAN.pdf
29-11-2024	A proposed floor plan	FLOOR PLAN.pdf
29-11-2024	Proposed elevation plan	ELEVATION.pdf
29-11-2024	Additional Document	AX385769J.pdf
29-11-2024	Additional Document	CURRENT PLAN OF SUB NOV 2024.pdf
29-11-2024	Overlay Requirements	ESO 42.01-s4.pdf

Remember it is against the law to provide false or misleading information, which could result in a heavy fine and cancellation of the permit

Lodged By

Site User	Hayley Woodall FRENKEN HOMES	194 Sladen street, cranbourne VIC 3977	W: 03-5995-1655 E: info@frenkenhomes.com.au
Submission Date	29 November 2024 - 11:46:AM		

Declaration

By ticking this checkbox, I, Hayley Woodall, declare that all the information in this application is true and correct; and the Applicant and/or Owner (if not myself) has been notified of the application.



Civic Centre
20 Siding Avenue, Officer, Victoria

Council's Operations Centre (Depot)
Purton Road, Pakenham, Victoria

Postal Address
Cardinia Shire Council
P.O. Box 7, Pakenham VIC, 3810
Email: mail@cardinia.vic.gov.au

Monday to Friday
8.30am–5pm
Phone: 1300 787 624
After Hours: 1300 787 624
Fax: 03 5941 3784

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.



Civic Centre
20 Siding Avenue, Officer, Victoria

Council's Operations Centre (Depot)
Purton Road, Pakenham, Victoria

Postal Address
Cardinia Shire Council
P.O. Box 7, Pakenham VIC, 3810
Email: mail@cardinia.vic.gov.au

Monday to Friday 8.30am–
5pm
Phone: 1300 787 624
After Hours: 1300 787 624
Fax: 03 5941 3784

Request to amend a current planning permit application

This form is used to request an amendment to an application for a planning permit that has already been lodged with Council, but which has not yet been decided. This form can be used for amendments made before any notice of the application is given (pursuant to sections 50 / 50A of the *Planning and Environment Act 1987*) or after notice is given (section 57A of the Act).

PERMIT APPLICATION DETAILS

Application No.:	
Address of the Land:	

APPLICANT DETAILS

Name:	
Organisation:	
Address:	
Phone:	
Email:	

AMENDMENT TYPE


Under which section of the Act is this amendment being made? (select one)	
Section 50 – Amendment to application at request of applicant before notice:	
Section 50A - Amendment to application at request of responsible authority before notice:	
Section 57A – Amendment to application after notice is given:	

AMENDMENT DETAILS

What is being amended? (select all that apply)		
What is being applied for	Plans / other documents	Applicant / owner details
Land affected	Other	
Describe the changes. If you need more space, please attach a separate page.		

Specify the estimated cost of any development for which the permit is required:		
Not applicable	Unchanged	New amount

DECLARATION

I declare that all the information in this request is true and correct and the owner (if not myself) has been notified of this request to amend the application.	
Name:	
Signature:	
Date:	

LODGEMENT

<p>Please submit this form, including all amended plans/documents, to mail@cardinia.vic.gov.au</p> <p>You can also make amendments to your application via the Cardinia ePlanning Portal at https://eplanning.cardinia.vic.gov.au/</p> <p>If you have any questions or need help to complete this form, please contact Council's Statutory Planning team on 1300 787 624.</p>
--

IMPORTANT INFORMATION

<p>It is strongly recommended that before submitting this form, you discuss the proposed amendment with the Council planning officer processing the application.</p> <p>Please give full details of the nature of the proposed amendments and clearly highlight any changes to plans (where applicable). If you do not provide sufficient details or a full description of all the amendments proposed, the application may be delayed.</p> <p>No application fee for s50/s50A requests unless the amendment results in changes to the relevant class of permit fee or introduces new classes of permit fees. The fee for a s57A request is 40% of the relevant class of permit fee, plus any other fees if the amendment results in changes to the relevant class (or classes) of permit fee or introduces new classes of permit fees. Refer to the <i>Planning and Environment (Fees) Regulations 2016</i> for more information.</p> <p>The amendment may result in a request for more under section 54 of the Act and/or the application requiring notification (or re-notification). The costs associated with notification must be covered by the applicant.</p> <p>Council may refuse to amend the application if it considers that the amendment is so substantial that a new application for a permit should be made.</p> <p>Any material submitted with this request, including plans and personal information, will be made available for public viewing, including electronically, and copies may be made for interested parties for the purpose of enabling consideration and review as part of a planning process under the <i>Planning and Environment Act 1987</i>.</p>
--

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

LOT 210 NO 8 MONTEREY WAY, PAKENHAM

FURTHER INFORMATION REQUIRED.....

1.0 Title Attached

2.0 DAP approval and stamped plans attached

3.0 (A) Covenant PS902144W

Restriction A – Approval has been obtained from the Design Assessment Panel.

Restriction B – No party walls exist.

Section 173 Agreement AX385769J

3.0 (B) Design Guidelines have been complied with as design approval has been obtained. We have satisfied their requirements including casual surveillance, building setbacks, water saving options and design including variety, articulation, colours, materials, textures, roof design, car accommodation, height restrictions and site coverage.

Restriction A – Approval has been obtained from the Design Assessment Panel.

Restriction B – No party walls exist.

Section 173 Agreement AX385769J

There is no vegetation on the land apart from grass / weeds which the owner will maintain along with any future installed landscaping. Developer design approval has been obtained.

The owner is obliged to comply with all things necessary as per the agreement.

PRELIMINARY ASSESSMENT COMMENT RESPONSES.....

Below is from other job.....

1 – Section 50 Form completed

2 – No outbuildings to note.

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

REGISTER SEARCH STATEMENT (Title Search) Transfer of Land Act 1958

VOLUME 12580 FOLIO 628

Security no : 124120252977V
Produced 29/11/2024 11:07 AM

LAND DESCRIPTION

Lot 210 on Plan of Subdivision 902144W.
PARENT TITLES :
Volume 12330 Folio 800 Volume 12580 Folio 422
Created by instrument PS902144W 01/11/2024

REGISTERED PROPRIETOR

Estate Fee Simple
Joint Proprietors

[Redacted Proprietor Name]

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

ENCUMBRANCES, CAVEATS AND NOTICES

[Redacted Encumbrance]

[Redacted Encumbrance]

[Redacted Encumbrance]

[Redacted Encumbrance]

DIAGRAM LOCATION

SEE PS902144W FOR FURTHER DETAILS AND BOUNDARIES

ACTIVITY IN THE LAST 125 DAYS

NUMBER		STATUS	DATE
PS902144W (B)	[Redacted]	Registered	01/11/2024
AY626064C (E)	[Redacted]	Registered	22/11/2024
AY626065A (E)	[Redacted]	Registered	22/11/2024
AY626066X (E)	[Redacted]	Registered	22/11/2024

-----END OF REGISTER SEARCH STATEMENT-----

Additional information: (not part of the Register Search Statement)

Street Address: 8 MONTEREY WAY PAKENHAM VIC 3810

ADMINISTRATIVE NOTICES

NIL

[Redacted Administrative Notice]

REGISTER SEARCH STATEMENT (Title Search) Transfer of Land Act 1958

Page 2 of 2

DOCUMENT END

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.



Department of Environment, Land, Water & Planning

Electronic Instrument Statement

Copyright State of Victoria. No part of this publication may be reproduced except as permitted by the Copyright Act 1968 (Cth), to comply with a statutory requirement or pursuant to a written agreement. The information is only valid at the time and in the form obtained from the LANDATA REGD TM System. None of the State of Victoria, its agents or contractors, accepts responsibility for any subsequent publication or reproduction of the information.

The Victorian Government acknowledges the Traditional Owners of Victoria and pays respects to their ongoing connection to their Country, History and Culture. The Victorian Government extends this respect to their Elders, past, present and emerging.

Produced 19/11/2024 11:11:39 AM

Status	Registered	Dealing Number	AX385769J
Date and Time Lodged	25/10/2023 12:57:26 PM		

Lodger Details

Lodger Code	21884L
Name	SETTLE CONNECT PTY LTD
Address	
Lodger Box	
Phone	
Email	
Reference	Cardinia (12330/801)

APPLICATION TO RECORD AN INSTRUMENT

Jurisdiction	VICTORIA
--------------	----------

Privacy Collection Statement

The information in this form is collected under statutory authority and used for the purpose of maintaining publicly searchable registers and indexes.

Estate and/or Interest

FEE SIMPLE

Land Title Reference

12330/800
12330/801

Instrument and/or legislation

RECORD - AGREEMENT - SECTION 173
Planning & Environment Act - section 173

Applicant(s)

Name	CARDINIA SHIRE COUNCIL
Address	
Property Name	CARDINIA SHIRE OFFICE
Street Number	20
Street Name	SIDING
Street Type	AVENUE
Locality	OFFICER
State	VIC

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.



Department of Environment, Land, Water & Planning

Electronic Instrument Statement

Postcode 3809

Additional Details

Refer Image Instrument

The applicant requests the recording of this Instrument in the Register.

Execution

1. The Certifier has taken reasonable steps to verify the identity of the applicant or his, her or its administrator or attorney.
2. The Certifier holds a properly completed Client Authorisation for the Conveyancing Transaction including this Registry Instrument or Document.
3. The Certifier has retained the evidence supporting this Registry Instrument or Document.
4. The Certifier has taken reasonable steps to ensure that this Registry Instrument or Document is correct and compliant with relevant law and any Prescribed Requirement.

Executed on behalf of	CARDINIA SHIRE COUNCIL
Signer Name	[REDACTED]
Signer Organisation	DYE & DURHAM LEGAL PTY LTD
Signer Role	AUSTRALIAN LEGAL PRACTITIONER
Execution Date	25 OCTOBER 2023

File Notes:

NIL

This is a representation of the digitally signed Electronic Instrument or Document certified by Land Use Victoria.

Statement End.

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.



Imaged Document Cover Sheet

The document following this cover sheet is an imaged document supplied by LANDATA®, Secure Electronic Registries Victoria.

Document Type	Instrument
Document Identification	AX385769J
Number of Pages (excluding this cover sheet)	17
Document Assembled	19/11/2024 11:11

Copyright and disclaimer notice:

© State of Victoria. This publication is copyright. No part may be reproduced by any process except in accordance with the provisions of the Copyright Act 1968 (Cth) and for the purposes of Section 32 of the Sale of Land Act 1962 or pursuant to a written agreement. The information is only valid at the time and in the form obtained from the LANDATA® System. None of the State of Victoria, LANDATA®, Secure Electronic Registries Victoria Pty Ltd (ABN 86 627 986 396) as trustee for the Secure Electronic Registries Victoria Trust (ABN 83 206 746 897) accept responsibility for any subsequent release, publication or reproduction of the information.

The document is invalid if this cover sheet is removed or altered.

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

ement

of the
ct 1987

Council

and

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

Ref: DV:NB:1050250

Doc ID 1115801193/v1

Level 8, 47 Collins Street, Melbourne VIC 3000 Australia
PO Box 3, Collins Street West VIC 3007 Australia
DX 554 Melbourne

Telephone +61 3 8644 3500
Facsimile 1300 365 323 (Australia) +61 3 9034 3257 (International)
hwlebsworth.com.au

Table of contents

1. Definitions and interpretation clauses	2
2. Owner's obligations	5
3. Further obligations	5
4. Agreement under Section 173 of the Act	6
5. Owner's warranties	7
6. Successors in title	7
7. Notices	7
8. Miscellaneous	8
Schedule	10
Executed as a deed	11
Schedule 1	12
Schedule 2	13

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

Deed of Agreement

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

Date 06/10/2023

Parties **Cardinia Shire Council**
of 20 Siding Avenue, Officer 3809

- Recitals
- A. Council is the Responsible Authority pursuant to the Act administration and enforcement of the Planning Scheme, which applies to the Subject Land.
 - B. The Owner is or is entitled to be the registered proprietor of the Subject Land, which is the land over which this Agreement is intended to be registered.
 - C. On 19 December 2017 Council issued Planning Permit No. T160690 (**Planning Permit**), which allows for the subdivision of the Subject Land, associated works, fencing, removal of native vegetation and altering access to a road in a Road Zone Category 1, generally in accordance with the approved plans.
 - D. On 9 June 2021 Council amended the Planning Permit (T160690-2) (**Amended Planning Permit**).
 - E. Condition 41 of the Amended Planning Permit provides that:

Prior to the issuing of a Statement of Compliance for each stage, the owner must enter into an agreement pursuant to Section 173 of the Planning and Environment Act 1987 to provide for the following:
 - a) *A plan of subdivision to show the location and dimensions of the plantation reserve as well as the building envelopes.*
 - b) *A requirement that each land owner must maintain the*

plantation reserve in perpetuity at the owner's cost. A separate maintenance/weed control schedule is required.

- c) *A requirement that any fencing within the plantation reserve must be wire or similar material to the satisfaction of the Responsible Authority.*
- d) *A requirement that each lot affected by the plantation reserve must comply with the relevant Building Design Guidelines registered on title.*

F. The Parties have agreed to enter into this Agreement:

- (a) to give effect to the requirements of the Amended Planning Permit;
- (b) that the Building Envelopes referred to in this Agreement relate only to the building envelopes for the lots abutting the plantation reserve on the eastern boundary of the Subject Land; and
- (c) to achieve and advance the objectives of planning in Victoria and the objectives of the Planning Scheme in respect of the Subject Land.

This deed witnesses that in consideration of, among other things, the mutual promises contained in this deed the parties agree as follows:

1. Definitions and interpretation clauses

1.1 Definitions

In this deed the following definitions apply:

Act means the *Planning and Environment Act 1987* (Vic).

Agreement means this Deed of Agreement and any Agreement executed by the Parties expressed to be supplemental to this Agreement.

Building Design Guidelines means the Building Design Guidelines required by conditions 6 and 7 of the Planning Permit.

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

Building Envelopes	means the building envelopes for the lots abutting the plantation reserve on the eastern boundary of the Subject Land.
Building Envelope Plan	means the plan showing the location and dimensions of the Building Envelopes attached at Schedule 1.
Business Day	means a day that is not a Saturday, Sunday or public holiday in Melbourne.
Claim	means any claim, action, proceeding or demand made against the person concerned, however it arises and whether it is present or future, fixed or unascertained, actual or contingent.
Council	means Cardinia Shire Council in its capacity as responsible authority.
Development	means the buildings and works authorised under the Planning Permit.
Endorsed Plans	means the plans and/or other documents that are endorsed pursuant to the Planning Permit from time to time.
Loss	means any loss, damage, cost, expense or liability incurred by the person concerned, however it arises and whether it is present or future, fixed or unascertained, actual or contingent.
Owner	means the person or persons registered or entitled from time to time to be registered by the Registrar of Titles as proprietor or proprietors of an estate in fee simple in the Subject Land or any part of it and includes a Mortgagee-in-possession.
Party or Parties	means the Owner and Council under this Agreement as appropriate.
Planning Permit	means Planning Permit No. T160690 issued by Council on 19 December 2017 referred to in Background C of this Agreement, and as amended from time to time (currently T160690-2 issued on 9 June 2021) and including any Endorsed Plans.

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

- Planning Scheme** means the Cardinia Planning Scheme and any other Planning Scheme which applies to the Subject Land.
- Plantation Reserve** means the area marked 'plantation reserve' forming part of the Subject Land as detailed in the Building Envelope Plan.
- Subject Land** means Volume 12330 Folio 801 (Lot 3 on Plan of Subdivision 6710) and Volume 12330 Folio 800 (Lot 2 on Plan of Subdivision 86652). Any reference to the Subject Land in this Agreement includes any lot created by the subdivision of the Subject Land or any part of it.
- VCAT** means the Victorian Civil and Administrative Tribunal.
- Vegetation Plan** means the vegetation plan attached at Schedule 2..

1.2 Interpretation

- (a) In this document, unless the context otherwise requires:
- (i) The singular includes the plural and vice versa.
 - (ii) A reference to a gender includes a reference to each other gender.
 - (iii) A reference to a person includes a reference to a firm, corporation or other corporate body and that person's successors in law.
 - (iv) If a Party consists of more than one person this Agreement binds them jointly and each of them severally.
 - (v) A term used in this Agreement has its ordinary meaning unless that term is defined in this Agreement. If a term is not defined in this Agreement and it is defined in the Act it has the meaning as defined in the Act.
 - (vi) A reference to an Act, Regulation or the Planning Scheme includes any Acts, Regulations or amendments amending, consolidating or replacing the Act, Regulation or Planning Scheme.
 - (vii) The introductory clauses to this Agreement are and will be deemed to form part of this Agreement.
 - (viii) Headings are for guidance only and do not affect the interpretation of this Agreement.

- (b) The obligations of the Owner under this Agreement, will take effect as separate and several covenants which are annexed to and run at law and equity with the Subject Land; and
 - (i) bind the Owner, its successors, transferees and permitted assigns, the registered proprietor or proprietors for the time being of the Subject Land; and
 - (ii) if the Subject Land is subdivided further, this Agreement must be read and applied so that each subsequent Owner of a lot is only responsible for those covenants and obligations which relate to that Owner's lot.

2. Owner's obligations

2.1 Plans showing the location of the Plantation Reserve and the Building Envelopes

The Owner covenants and agrees that the Building Envelope Plan shows the location and dimensions of the Plantation Reserve, as well as, the relevant Building Envelopes.

2.2 Maintenance of the Plantation Reserve

The Owner covenants and agrees that it will maintain the plantation reserve:

- (a) in perpetuity;
- (b) at the its own cost; and
- (c) in accordance with the Vegetation Plan.

2.3 Fencing within the Plantation Reserve

The Owner covenants and agrees to construct all fencing within the Plantation Reserve of wire or similar material to the satisfaction of the Responsible Authority.

2.4 Building Design Guidelines

The Owner covenants and agrees that the construction of buildings on each lot affected by the Plantation Reserve must comply with the Building Design Guidelines.

3. Further obligations

3.1 Notice and registration

The Owner will bring this Agreement to the notice of all prospective purchasers, Mortgagees, lessees, charges, transferees and assigns of the Subject Land.

3.2 Giving effect to this Agreement

The Owner will do all things necessary to give effect to this Agreement, including executing any further documents and will comply with its obligations under this Agreement.

3.3 Recording by Registrar of Titles

The Owner will consent to Council making application to the Registrar of Titles to make a recording of this Agreement in the Register on the Certificate of Title of the Subject Land in accordance with s181 of the Act and do all things necessary to enable Council to do so including signing any further agreement, acknowledgement or document or procuring the consent to this Agreement of any Mortgagee or caveator to enable the recording to be made in the Register under that section.

3.4 Council's costs to be paid

- (a) The Owner will immediately pay to Council, Council's reasonable costs and expenses (including legal expenses) of and incidental to the preparation, drafting, finalisation, engrossment, execution, registration and enforcement of this Agreement which are and until paid will remain a debt due to Council by the Owner.
- (b) If in dispute, Council may have the costs assessed by the Law Institute of Victoria Costing Service and the Parties will be bound by any assessment, and the cost of any assessment will be paid equally by the Parties.

3.5 Mortgagee to be Bound

The Owner covenants to obtain the consent of any Mortgagee to be bound by the covenants in this Agreement if the Mortgagee becomes Mortgagee in possession of the Subject Land.

3.6 Covenants run with the Subject Land

The Owner's obligation in this Agreement are intended to take effect as covenants which shall be annexed to and run at law and in equity with the Subject Land and every part of it, and bind the Owner and its successors, assignees and transferees, the registered proprietor or proprietors for the time being of the Subject Land and every part of the Subject Land.

4. Agreement under Section 173 of the Act

Council and the Owner agree without limiting or restricting their respective powers to enter into this Agreement and, insofar as it can be so treated, this Agreement is made pursuant to section 173 of the Act.

5. Owner's warranties

Without limiting the operation or effect which this Agreement has, the Owner warrants that apart from the Owner and any other person which has consented in writing to this Agreement, no other person has any interest, either legal or equitable, in the Subject Land which may be affected by this Agreement.

6. Successors in title

6.1 Successors in title

Without limiting the operation or effect which this Agreement has, the Owner must ensure that until such time as a memorandum of this Agreement is registered on the title to the Subject Land, successors in title shall be required to:

- (a) give effect to and do all acts and sign all documents which will require those successors to give effect to this Agreement; and
- (b) execute a deed agreeing to be bound by the terms of this Agreement.

7. Notices

7.1 Service

A notice or other communication required or permitted to be served by a Party on another Party must be in writing and may be served:

- (a) by delivering it personally to that Party;
- (b) by sending it by prepaid post addressed to that Party at the address set out in this Agreement or subsequently notified to each Party from time to time; or
- (c) by sending it by electronic mail to that Party using the email address set out in this Agreement or subsequently notified to each Party from time to time.

7.2 Time of service

A notice or other communication is deemed served:

- (a) if delivered, on the following business day;
- (b) if posted, on the expiration of two business days after the date of posting; or
- (c) if emailed, when the electronic communication becomes capable of being retrieved by the addressee at an electronic address designated by the addressee.

8. Miscellaneous

8.1 Commencement of Agreement

Unless otherwise provided in this Agreement, this Agreement commences from the date of this Agreement.

8.2 Default

- (a) If the Owner fails to comply with the provisions of this Agreement, Council may serve a notice on the Owner specifying the works, matters and things in respect of which the Owner is in default.
- (b) If the alleged default continues for 30 days after the service of such notice, Council may, by its officers, employees, agents and contractors, enter the Subject Land and ensure that the works, matters and things are carried out.
- (c) The costs incurred by the Council in undertaking the works as a result of the Owner's default will be payable by the Owner.

8.3 Ending of Agreement

This Agreement ends:

- (a) on the date that the Council confirms in writing that this Agreement can be ended; or
- (b) otherwise in accordance with the Act.

8.4 Application to Registrar

As soon as reasonably practicable after the Agreement has ended, Council will, at the request and at the cost of the Owner make application to the Registrar of Titles under s183(2) of the Act to cancel the recording of this Agreement on the register.

8.5 No fettering of Council's powers

It is acknowledged and agreed that this Agreement does not fetter or restrict the power or discretion of Council to make any decision or impose any requirements or conditions in connection with the granting of any planning approval or certification of any plans of subdivision applicable to the Subject Land or relating to any use or development of the Subject Land.

8.6 No waiver

Any time or other indulgence granted by Council to the Owner or any variation of the terms and conditions of this Agreement or any judgment or order obtained by Council against the Owner will not in any way amount to a waiver of any of the rights or remedies of Council in relation to the terms of this Agreement.

8.7 Severability

- (a) If a court, arbitrator, tribunal or other competent authority determines that a word, phrase, sentence, paragraph or clause of this Agreement is unenforceable, illegal or void then it must be severed and the other provisions of this Agreement will remain operative.
- (b) Clause 8.7(a) will not apply if to do so will materially affect the commercial arrangement formed by this Agreement.

8.8 Proper law

This Agreement is governed by and the Owner submits to the laws of the State of Victoria.

8.9 Counterparts

This Agreement may be executed in counterparts, and is binding on the parties upon the counterparts being exchanged. A copy of the original executed counterpart sent by email is to be treated as an original counterpart for all intents and purposes.

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

Schedule

Mortgagee's Consent

[REDACTED] as Mortgagee of registered Mortgage No AW944856J consents to the Owner entering into this Agreement and agrees to be bound by the terms and conditions of this Agreement as if it were the Owner of the Subject Land.

[REDACTED]
[REDACTED]
Signature of Director
Secretary

[REDACTED]
Print full name

[REDACTED]
Signature of Director/C

[REDACTED]
Print full name

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

Executed as a deed

Signed, sealed and delivered as a deed by the parties

[Redacted]

Manager Planning and Design, on behalf of)
Shire Council in the exercise of a)
conferred by an Instrument of Delegation)
presence of:)

[Redacted]

Signature of [Redacted]

[Redacted]

Name of witness
Execution of this document has been witnessed by me
in accordance with the requirements for witnessing by
audio-visual link under section 12 of the Electronic
Transactions (Victoria) Act 2000.
(Strike out if inapplicable)

[Redacted]

Name of witness
(BLOCK LETTERS)

[Redacted]

section 127 of the *Corporations Act 2001* (Cth)
by:

[Redacted]

Signature of Director and Company Secretary

[Redacted]

Signature of Director

[Redacted]

Full name (print)

[Redacted]

Full name (print)

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

Schedule 1

Building Envelope Plan




AX385769J

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will not disseminate the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

- LEGEND**
- Title boundary (approx.)
 - Pedestrian path
 - Shared path
 - Stage boundary
 - Stage numbers
 - Entry point
 - Existing contours (5m interval)
 - Lots
 - Substation kiosk
 - Superlot
 - Pakenham road widening
 - Naturestrip (indicative)
 - Road pavement (indicative)
 - Reserve (Council easement)
 - Tree reserve
 - Drainage reserve
 - Plantation Reserve (back of lot) = 7m
 - Turning direction
 - Trees & TPZ - via Ecolink
 - Trees to be removed
 - 4m Paper Road
 - Building Envelope

Proposed site entry to the satisfaction of and at no cost to the Head, Transport for Victoria
 Proposed site entry
 Per drawing: 2000490-FLP-01-2-1.pdf
 Refer to road section for Pakenham Road



Pakenham Road - Cross Section

- Notes:**
- This plan is subject to Council approval.
 - All dimensions and areas are subject to survey and final computations.
 - The drainage reserve shown has been preliminarily sized for the treatment and detention of stormwater to Council requirements. The layout and area required will be subject to engineering detail design and Council approval.
 - All roads are 16m local access level 1 unless noted otherwise.
 - Road pavement is indicative only and subject to detailed engineering design.
 - Arc dimensions shown are length of arc (not chord).

Total number of lots	203
Stage 1	31
Stage 2	34
Stage 3	18
Stage 4	44
Stage 5	41
Stage 6	34
Stage 7*	1


* Stage includes 1 Superlot

Lot Schedule by Area		
Lot Size	Number of Lots	%
0-299m ²	42	20.8
300-399m ²	56	27.7
400-499m ²	81	40.1
500-599m ²	3	1.5
600-699m ²	0	0.0
700m ² +	20	9.9
Total	202	100

* Table does not include superlot

Site (Approx.)	15,307 ha
* Standard Density Lots	7,515 ha
* Medium Density Lots	1,021 ha
* Superlot	1,168 ha
* Kiosk	0,009 ha
* Tree Reserve	0,165 ha
* Non-Arterial Roads	3,274 ha
Arterial Roads (Pakenham road widening)	0,693 ha
Reserve (Council Easement)	0,580 ha
Drainage Reserve	0,884 ha
Net Developable Area	13,150 ha
Lot Yield (Standard Density)	160 lots 470m ² average lot size
Lot Yield (Medium Density)	42 lots 243m ² average lot size
** Lot Yield (Overall)	202 lots @ 16,9 lots per ha 423m ² average lot size
Superlot	1
Total Number of Lots (Inc. 1 superlot)	203

* Indicates inclusion in NDA



Subdivision Plan
 110 Pakenham Road, Pakenham

APPROVED AMENDED PLAN
 PLANNING AND ENVIRONMENT ACT 1987
 CARDINA PLANNING SCHEME
 PERMIT No: T160690-2
 SHEET: 1 OF 1
 APPROVED BY: Dean Heusler
 CARDINA SHIRE COUNCIL
 DATE: Monday, 10 October 2022

12	12/11/2021	Pakenham road layout	KT	KT	Date: 01.09.2022
13	01/12/2021	Added building envelopes	KT	KT	Version No: 16
14	01/12/2021	Updated road and staging boundary	KT	KT	Job No: 2000490
15	01/12/2021	Updated staging boundary	KT	KT	Scale (A1): 1:1000
16	19/11/2024	Updated lot numbers, building envelope and tables	OK	KT	(A3): 1:2000
Version	Date	Description	Drafted	Approved	

K:\CUBS DATA\2000490-110 PAKENHAM ROAD\UDICAD\2000490-FLP-01-2-1-BASE.DWG

Schedule 2

Vegetation Plan

AX385769J

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.





CODE	BOTANICAL NAME	COMMON NAME	NATURAL HEIGHT	PLANTED POT HEIGHT	INSTALLED MIN. HEIGHT	QTY
1	<i>Acacia saligna</i>	Black Wattle	3.0m	3.0m	3.0m	30
2	<i>Callerya reticulata</i>	Callerya	3.0m	3.0m	3.0m	30
3	<i>Leptosiphon juncea</i>	Leptosiphon	3.0m	3.0m	3.0m	30
4	<i>Leptosiphon juncea</i>	Leptosiphon	3.0m	3.0m	3.0m	30
5	<i>Leptosiphon juncea</i>	Leptosiphon	3.0m	3.0m	3.0m	30
6	<i>Leptosiphon juncea</i>	Leptosiphon	3.0m	3.0m	3.0m	30
7	<i>Leptosiphon juncea</i>	Leptosiphon	3.0m	3.0m	3.0m	30
8	<i>Leptosiphon juncea</i>	Leptosiphon	3.0m	3.0m	3.0m	30
9	<i>Leptosiphon juncea</i>	Leptosiphon	3.0m	3.0m	3.0m	30
10	<i>Leptosiphon juncea</i>	Leptosiphon	3.0m	3.0m	3.0m	30
11	<i>Leptosiphon juncea</i>	Leptosiphon	3.0m	3.0m	3.0m	30

CODE	BOTANICAL NAME	COMMON NAME	DBH (mm)	T20 (m)
1	<i>Leptosiphon juncea</i>	Leptosiphon	42	3.0
2	<i>Leptosiphon juncea</i>	Leptosiphon	42	3.0
3	<i>Leptosiphon juncea</i>	Leptosiphon	42	3.0
4	<i>Leptosiphon juncea</i>	Leptosiphon	42	3.0
5	<i>Leptosiphon juncea</i>	Leptosiphon	42	3.0
6	<i>Leptosiphon juncea</i>	Leptosiphon	42	3.0
7	<i>Leptosiphon juncea</i>	Leptosiphon	42	3.0
8	<i>Leptosiphon juncea</i>	Leptosiphon	42	3.0
9	<i>Leptosiphon juncea</i>	Leptosiphon	42	3.0
10	<i>Leptosiphon juncea</i>	Leptosiphon	42	3.0
11	<i>Leptosiphon juncea</i>	Leptosiphon	42	3.0



NOTES
 1. Indigenous tree and shrub planting is indigenous as per EVC Number 128, Grassy Forest (Highlands - Southern Fall (Blorngong))
 2. Plant densities for trees, medium shrubs and small shrubs have been calculated in accordance with the DSE Native Revegetation Planning Standards



A STANDARD TREE PLANTING DETAIL (45L POTS)
 Scale 1:20 @ A1

B TUBESTOCK PLANTING WITH MULCH AND GUARD
 Scale 1:20 @ A1

MAINTENANCE / WEED CONTROL SCHEDULE

SHORT TERM (1-2 years) - Lot Owner's Responsibility

1. Carry out regular maintenance for litter removal and weeding to <1%.
2. Ensure plants are establishing with an 80% survival rate.
3. Replace dead or dying plants on an as needed basis during favourable planting conditions (not in summer or mid-winter).

MEDIUM TERM (3-5 years) - Lot Owner's Responsibility

1. Carry out regular maintenance for litter removal and weeding to <1%.
2. Monitor natural regeneration and remove any weeds posing a threat of crowding out native plants.
3. Undertake infill planting/replacement at 1% p.a.

LONG TERM (5yrs +) - Lot Owner's Responsibility

1. Carry out regular maintenance for litter removal and weeding to <1%.
2. Monitor natural regeneration and remove any weeds posing a threat of crowding out native plants.

*Each land owner must maintain the plantation reserve in perpetuity at the owner's cost.


GENERAL NOTES

1. The Contractor must verify all dimensions on site and immediately report any discrepancies to the Project Manager.
2. The site is to be cleared of all debris and builder's rubble.
3. All weed species on site shall be eradicated.
4. All planting shall be completed prior to ordering.
5. All plant species shall be true to type and there should be no alterations or substitutions of nominated species or cultivars without the written consent of the Landscape Architect.
6. All plant stock must be checked by the Contractor and must be healthy and disease free.
7. Planting must be undertaken in accordance with sound horticultural practices.
8. Supply and install 20mm diameter 80mm depth approved fine grade excumulch to all tree watering bowls.
9. All plants must be thoroughly hand watered immediately after planting. The Contractor must check current water restrictions and ensure there is an adequate supply of water suitable for plants.

01 NORTHERN PLAN (01)
 Scale 1:500 @ A1

02 MIDDLE PLAN (02)
 Scale 1:500 @ A1

03 SOUTHERN PLAN (03)
 Scale 1:500 @ A1



FOR APPROVAL

01 NORTHERN PLAN (01) Scale 1:500 @ A1

02 MIDDLE PLAN (02) Scale 1:500 @ A1

03 SOUTHERN PLAN (03) Scale 1:500 @ A1

THE RISE - PAKENHAM
 Plantation Reserve Landscape Plan

Project Name: The Rise - Pakenham
 Project No: 2000490-01
 Drawing No: L01
 Date: 13/09/2024

Prepared By: [Redacted]
 Checked By: [Redacted]
 Drawn By: [Redacted]
 Approved By: [Redacted]

Beveridge Williams
 development & environment consultants

1 Glenelg Road
 Glenelg VIC 3144
 PH 03 9524 8858
 www.beveridgewilliams.com.au

Scale: 1:500 @ A1
 Project Ref: 2000490-01
 Drawing No: L01
 Revision: B

DATE: 13/09/2024

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.



Imaged Document Cover Sheet

The document following this cover sheet is an imaged document supplied by LANDATA®, Secure Electronic Registries Victoria.

Document Type	Plan
Document Identification	PS902144W
Number of Pages (excluding this cover sheet)	5
Document Assembled	29/11/2024 11:07

Copyright and disclaimer notice:

© State of Victoria. This publication is copyright. No part may be reproduced by any process except in accordance with the provisions of the Copyright Act 1968 (Cth) and for the purposes of Section 32 of the Sale of Land Act 1962 or pursuant to a written agreement. The information is only valid at the time and in the form obtained from the LANDATA® System. None of the State of Victoria, LANDATA®, Secure Electronic Registries Victoria Pty Ltd (ABN 86 627 986 396) as trustee for the Secure Electronic Registries Victoria Trust (ABN 83 206 746 897) accept responsibility for any subsequent release, publication or reproduction of the information.

The document is invalid if this cover sheet is removed or altered.

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

<h1>PLAN OF SUBDIVISION</h1>	<h2>EDITION 1</h2>	<h1>PS902144W</h1>
------------------------------	--------------------	--------------------

<p>LOCATION OF LAND</p> <p>PARISH: NAR NAR GOON TOWNSHIP: PAKENHAM SECTION: —</p> <p>CROWN ALLOTMENT: 32(PT), 33(PT) & 34(PT)</p> <p>TITLE REFERENCE: VOL. 12580 FOL. 422 VOL. 12330 FOL. 800</p> <p>LAST PLAN REFERENCE: PS848743W (LOT A) LP86652 (LOT 2)</p> <p>POSTAL ADDRESS: 14 SUNNY VISTA (at time of subdivision) PAKENHAM ROAD PAKENHAM 3810</p> <p>MGA CO-ORDINATES: E: 366 200 ZONE: 55 (of approx centre of land in plan) N: 5 786 450 GDA 2020</p>	<p>Council Name: Cardinia Shire Council</p> <p>Council Reference Number: S21-147 Planning Permit Reference: T160690-2 SPEAR Reference Number: S182118A</p> <p>Certification</p> <p>This plan is certified under section 11 (7) of the Subdivision Act 1988 Date of original certification under section 6 of the Subdivision Act 1988: 16/08/2023</p> <p>Public Open Space</p> <p>A requirement for public open space under section 18 or 18A of the Subdivision Act 1988 has been made and the requirement has not been satisfied at Certification</p> <p>Digitally signed by: Sonia Higgins for Cardinia Shire Council on 27/06/2024</p> <p>Statement of Compliance issued: 28/10/2024</p> <p>Public Open Space</p> <p>A requirement for public open space under section 18 or 18A of the Subdivision Act 1988 has been made and the requirement has been satisfied at Statement of Compliance</p>
--	---

VESTING OF ROADS AND/OR RESERVES	NOTATIONS
---	------------------

IDENTIFIER	COUNCIL/BODY/PERSON	NOTATIONS
ROAD R1	CARDINIA SHIRE COUNCIL	<p>LOTS 1 TO 200 (BOTH INCLUSIVE) HAVE BEEN OMITTED FROM THIS PLAN.</p> <p>LOTS IN THIS PLAN MAY BE AFFECTED BY ONE OR MORE RESTRICTIONS. FOR DETAILS OF RESTRICTIONS INCLUDING BURDENED LOTS & BENEFITING LOTS, SEE CREATION OF RESTRICTIONS ON SHEET 5</p> <p>OTHER PURPOSE OF PLAN: TO REMOVE THAT PART OF THE SEWERAGE EASEMENT CREATED AS E-3 ON PS848743W CONTAINED WITHIN MONTEREY WAY ON THIS PLAN.</p> <p>GROUND FOR REMOVAL OF EASEMENT: AGREEMENT FROM ALL INTERESTED PARTIES (SECTION 6(1)K SUBDIVISION ACT 1988)</p> <p style="text-align: center;">WARNING: The restrictive covenant(s)/restriction(s) in this plan may have been varied or removed. For current information, please refer to the relevant folio(s) of the Register, noting section 88(3) of the Transfer of Land Act 1958</p>

NOTATIONS	
------------------	--

<p>DEPTH LIMITATION: DOES NOT APPLY</p> <p>This is a SPEAR plan.</p> <p>STAGING: This is not a staged subdivision. Planning Permit No. T160690</p> <p>SURVEY: This plan is based on survey. This survey has been connected to permanent marks No(s). 89, 199, 213, 285, 286, 287, 295, 319, 320, 354, 355, 363, 674, 675</p> <div style="border: 1px solid black; padding: 2px; margin-top: 5px;"> <p>Estate: The Rise - Pakenham Phase No.: 02 No. of Lots: 34 + Lot B PHASE AREA: 1.772ha</p> </div>	
--	--

EASEMENT INFORMATION

LEGEND: A - Appurtenant Easement E - Encumbering Easement R - Encumbering Easement (Road)

SECTION 12(2) OF THE SUBDIVISION ACT 1988 APPLIES TO LOTS 213 TO 216 (BOTH INCLUSIVE) AND 218 TO 221 (BOTH INCLUSIVE) IN THIS PLAN.

Easement Reference	Purpose	Width (Metres)	Origin	Land Benefited/In Favour Of
E-1, E-4 E-2 E-2, E-3 E-7, E-5 E-7, E-6 E-4	PIPELINE DRAINAGE SEWERAGE SEWERAGE DRAINAGE SUPPLY OF WATER (THROUGH UNDERGROUND PIPES)	24.38 SEE DIAG SEE DIAG SEE DIAG SEE DIAG 6	INST. D613929 PS848743W PS848743W THIS PLAN THIS PLAN PS848743W	VICTORIA PIPELINES COMMISSION CARDINIA SHIRE COUNCIL SOUTH EAST WATER CORPORATION SOUTH EAST WATER CORPORATION CARDINIA SHIRE COUNCIL SOUTH EAST WATER CORPORATION

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

<p>Beveridge Williams development & environment consultants Melbourne ph : 03 9524 8888 www.beveridgewilliams.com.au</p>	<p>SURVEYORS FILE REF: 2000490/02 2000490-02-PS-V6.DWG</p> <p>Digitally signed by: ADRIAN JAMES FREEMAN, Licensed Surveyor, Surveyor's Plan Version (6), 03/06/2024, SPEAR Ref: S182118A</p>	<p>ORIGINAL SHEET SIZE: A3</p>	<p>SHEET 1 OF 5</p>	<p>Land Use Victoria Plan Registered 10:25 AM 01/11/2024 Assistant Registrar of Titles</p>
--	--	---------------------------------------	---------------------	---

PS902144W





DIAGRAM NOT TO SCALE

DIAGRAM A NOT TO SCALE


DIAGRAM B NOT TO SCALE

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By using a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

BW Beveridge Williams
 development & environment consultants
 Melbourne ph : 03 9524 8888
 www.beveridgewilliams.com.au

SURVEYORS REF
2000490/02

SCALE
1 : 2000



ORIGINAL SHEET
SIZE: A3


SHEET 2


Digitally signed by: ADRIAN JAMES FREEMAN, Licensed Surveyor,
 Surveyor's Plan Version (6),
 03/06/2024, SPEAR Ref: S182118A

Digitally signed by:
 Cardinia Shire Council,
 27/06/2024,
 SPEAR Ref: S182118A


This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

PS902144W




 Beveridge Williams development & environment consultants Melbourne ph : 03 9524 8888 www.beveridgewilliams.com.au	SURVEYORS REFERENCE 2000490 /02	SCALE 1 : 500 LENGTHS ARE IN METRES	ORIGINAL SHEET SIZE: A3	SHEET 3
	Digitally signed by: Adrian James Freeman, Licensed Surveyor, Surveyor's Plan Version (6), 03/06/2024, SPEAR Ref: S182118A	Digitally signed by: Cardinia Shire Council, 27/06/2024, SPEAR Ref: S182118A		

PS902144W



This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

B



SEE SHEET 2

SEE SHEET 2

Beveridge Williams
development & environment consultants
Melbourne ph : 03 9524 8888
www.beveridgewilliams.com.au

SURVEYORS REFERENCE
2000490
/02

Scale 1:500
LENGTHS ARE IN METRES
5 0 5 10 15 20

ORIGINAL SHEET SIZE: A3
SHEET 4

Digitally signed by: ADRIAN JAMES FREEMAN, Licensed Surveyor, Surveyor's Plan Version (6), 03/06/2024, SPEAR Ref: S182118A

Digitally signed by: Cardinia Shire Council, 27/06/2024, SPEAR Ref: S182118A

SUBDIVISION ACT 1988
CREATION OF RESTRICTION 'A'

PS902144W

THE REGISTERED PROPRIETORS OF THE BURDENED LAND COVENANT WITH THE REGISTERED PROPRIETORS OF THE BENEFITED LAND AS SET OUT IN THE RESTRICTION WITH THE INTENT THAT THE BURDEN OF THE RESTRICTION RUNS WITH AND BINDS THE BURDENED LAND AND THE BENEFIT OF THE RESTRICTION IS ANNEXED TO AND RUNS WITH THE BENEFITED LAND.

LAND TO BENEFIT & TO BE BURDENED:

BURDENED LAND: LOTS 201 TO 234 (BOTH INCLUSIVE)
 BENEFITING LAND: LOTS 201 TO 234 (BOTH INCLUSIVE)

DESCRIPTION OF RESTRICTION:

THE REGISTERED PROPRIETOR OR PROPRIETORS FOR THE TIME BEING OF ANY BURDENED LOT ON THE PLAN OF SUBDIVISION SHALL NOT:

- (1) CONSTRUCT OR ALLOW TO BE CONSTRUCTED ANY BUILDING OR STRUCTURE OTHER THAN A BUILDING OR STRUCTURE THAT SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE RISE (PAKENHAM) ESTATE DESIGN GUIDELINES AS AMENDED FROM TIME TO TIME.

A COPY OF THE DESIGN GUIDELINES AND BUILDING ENVELOPE PLAN IS AVAILABLE at <http://www.beveridgewilliams.com.au/design-application/>

- (2) CONSTRUCT OR ALLOW TO BE CONSTRUCTED ANY BUILDING OR STRUCTURE ON THE LOT PRIOR TO:
 - (A) COPIES OF BUILDING PLANS, ELEVATION, ROOF PLANS, SITE PLANS (INCORPORATING SETBACKS FROM ALL BOUNDARIES, EXISTING CONTOURS, LANDSCAPED FINISHED FLOOR LEVELS AND SITE LEVELS, ALL PROPOSED DRIVEWAYS AND PATHS, DETAILS OF FENCES AND OUTBUILDINGS AND LANDSCAPING) AND SCHEDULES OF EXTERNAL COLOURS AND MATERIALS HAVE BEEN SUBMITTED VIA THE DESIGN PORTAL AT THE ABOVE ADDRESS OR SUCH OTHER ENTITY AS MAY BE NOMINATED BY THE DESIGN ASSESSMENT PANEL FROM TIME TO TIME;
 - (B) THE DESIGN ASSESSMENT PANEL OR SUCH OTHER ENTITY AS MAY BE NOMINATED BY THE DESIGN ASSESSMENT PANEL FROM TIME TO TIME HAVE GIVEN ITS WRITTEN APPROVAL TO THE PLANS PRIOR TO THE COMMENCEMENT OF WORKS.

VARIATION:

ANY VARIATION TO CONDITIONS 1 AND 2 OF RESTRICTION 'A' WILL REQUIRE THE CONSENT OF THE DESIGN ASSESSMENT PANEL.

EXPIRY:

THIS RESTRICTION CEASES TO HAVE EFFECT FOLLOWING AFTER EITHER;

- (i) THE ISSUE OF AN OCCUPANCY PERMIT UNDER THE BUILDING ACT 1993 (OR SIMILAR) IN RESPECT OF A BUILDING ON EVERY RESIDENTIAL LOT ON THIS PLAN.
- (ii) 31 DECEMBER 2039.

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

CREATION OF RESTRICTION 'B'

THE REGISTERED PROPRIETORS OF THE BURDENED LAND COVENANT WITH THE REGISTERED PROPRIETORS OF THE BENEFITED LAND AS SET OUT IN THE RESTRICTION WITH THE INTENT THAT THE BURDEN OF THE RESTRICTION RUNS WITH AND BINDS THE BURDENED LAND AND THE BENEFIT OF THE RESTRICTION IS ANNEXED TO AND RUNS WITH THE BENEFITED LAND.

LAND TO BENEFIT & TO BE BURDENED:

BURDENED LAND: LOTS 201 TO 234 (BOTH INCLUSIVE)
 BENEFITING LAND: LOTS 201 TO 234 (BOTH INCLUSIVE)

DESCRIPTION OF RESTRICTION:

THE REGISTERED PROPRIETOR OR PROPRIETORS FOR THE TIME BEING OF ANY BURDENED LOT ON THE PLAN OF SUBDIVISION SHALL NOT:

- 1) CONSTRUCT OR ALLOW TO BE CONSTRUCTED ANY BUILDING OR STRUCTURE WITH PARTY WALLS UNLESS THE PARTY WALLS ARE CONSTRUCTED SIMULTANEOUSLY WITH THE ABUTTING LOTS

EXPIRY:

THIS RESTRICTION CEASES TO HAVE EFFECT FOLLOWING AFTER EITHER;

- (i) THE ISSUE OF AN OCCUPANCY PERMIT UNDER THE BUILDING ACT 1993 (OR SIMILAR) IN RESPECT OF A BUILDING ON EVERY RESIDENTIAL LOT ON THIS PLAN.
- (ii) 31 DECEMBER 2039.

GENERAL NOTES
INTELLECTUAL PROPERTY AND USE OF THIS DOCUMENT
 □ THIS DOCUMENT HAS BEEN PREPARED FOR THE EXCLUSIVE USE OF THE CLIENT OF AC DESIGN & DRAFTING (THE DESIGNER), FOR THE PURPOSE EXPRESSLY NOTIFIED TO THE DESIGNER. ANY OTHER PERSON WHO USES OR RELIES ON THESE PLANS WITHOUT THE DESIGNERS WRITTEN CONSENT DOES SO AT THEIR OWN RISK AND NO RESPONSIBILITY IS ACCEPTED BY THE DESIGNER FOR SUCH USE AND/OR RELIANCE.
 □ THIS DOCUMENT IS TO BE READ IN CONJUNCTION WITH ALL DRAWINGS, DETAILS AND INFORMATION PROVIDED BY THE CONSULTANTS NAMED HEREIN, AND WITH ANY OTHER WRITTEN INSTRUCTIONS ISSUED IN THE COURSE OF THE CONTRACT.
 □ A BUILDING PERMIT IS REQUIRED PRIOR TO THE COMMENCEMENT OF THESE WORKS. THE RELEASE OF THIS DOCUMENT IS CONDITIONAL ON THE CLIENT OBTAINING THE REQUIRED BUILDING PERMIT.

MATERIALS AND TRADE PRACTICES
 □ ALL MATERIALS, CONSTRUCTION AND WORK PRACTICES SHALL COMPLY WITH BUT NOT BE LIMITED TO THE CURRENT ISSUE OF NATIONAL CONSTRUCTION CODE 2022 BUILDING CODE OF AUSTRALIA VOL. 2 (HEREAFTER REFERRED TO AS BCA), AND ALL RELEVANT CURRENT AUSTRALIAN STANDARDS REFERRED TO THEREIN.
 □ WORK AND SITE MANAGEMENT PRACTICES SHALL COMPLY WITH ALL RELEVANT LAWS AND BY-LAWS.
 □ IF ANY PERFORMANCE SOLUTION IS PROPOSED, IT SHALL BE ASSESSED AND APPROVED BY THE [RELEVANT BUILDING SURVEYOR/BUILDING CERTIFIER] AS MEETING BCA PERFORMANCE REQUIREMENTS PRIOR TO IMPLEMENTATION OR INSTALLATION.
 □ INSTALLATION OF ALL SERVICES SHALL COMPLY WITH THE RESPECTIVE SUPPLY AUTHORITY'S REQUIREMENTS.

VARIATIONS
 □ SHOULD ANY CONFLICT ARISE BETWEEN THESE PLANS AND BCA, AUSTRALIAN STANDARDS OR A MANUFACTURER'S INSTRUCTIONS, THIS DISCREPANCY SHALL BE REPORTED IMMEDIATELY TO THE DESIGNER, BEFORE ANY OTHER ACTION IS TAKEN.
 □ THE CLIENT AND/OR THE CLIENTS BUILDER SHALL NOT MODIFY OR AMEND THE PLANS WITHOUT THE KNOWLEDGE AND CONSENT OF THE DESIGNER, EXCEPT WHERE THE [RELEVANT BUILDING SURVEYOR/BUILDING CERTIFIER] MAKES MINOR NECESSARY CHANGES TO FACILITATE THE BUILDING PERMIT APPLICATION
 □ THE APPROVAL BY THE DESIGNER OF A SUBSTITUTE MATERIAL, WORK PRACTICE OR THE LIKE IS NOT AN AUTHORISATION FOR ITS USE OR A CONTRACT VARIATION. ANY VARIATIONS AND/OR SUBSTITUTIONS TO MATERIALS OR WORK PRACTICES SHALL BE ACCEPTED BY ALL PARTIES TO THE BUILDING CONTRACT AND, WHERE APPLICABLE, THE [RELEVANT BUILDING SURVEYOR/BUILDING CERTIFIER], PRIOR TO IMPLEMENTATION.

MEASUREMENTS
 □ FIGURED DIMENSIONS TAKE PRECEDENCE OVER SCALED DIMENSIONS.
 □ SITE PLAN MEASUREMENTS ARE IN METRES. ALL OTHER MEASUREMENTS ARE IN MILLIMETRES, UNLESS NOTED OTHERWISE.
 □ UNLESS NOTED OTHERWISE, DIMENSIONS ON FLOOR PLANS, SECTIONS AND EXTERNAL ELEVATIONS REPRESENT TIMBER FRAME AND STRUCTURAL MEMBERS, NOT FINISHED LININGS/CLADDING.
 □ WINDOW SIZES ARE NOMINAL ONLY. ACTUAL SIZE MAY VARY ACCORDING TO MANUFACTURER.
 □ THE BUILDER AND SUBCONTRACTORS SHALL CHECK AND VERIFY ALL DIMENSIONS, SETBACKS, LEVELS, SPECIFICATIONS, AND ALL OTHER RELEVANT DOCUMENTATION PRIOR TO THE COMMENCEMENT OF ANY WORKS. REPORT ALL DISCREPANCIES TO THE DESIGNER FOR CLARIFICATION.

SUPPLEMENTARY NOTES
SITE PROTECTION DURING THE CONSTRUCTION PERIOD
 □ PROTECTIVE OUTRIGGERS, FENCES, AWNINGS, HOARDING, BARRICADES AND THE LIKE SHALL BE INSTALLED WHERE NECESSARY TO GUARD AGAINST DANGER TO LIFE OR PROPERTY OR WHEN REQUIRED BY THE RELEVANT BUILDING SURVEYOR AND/OR COUNCIL.
 □ WHERE REQUIRED BY COUNCIL, THE BUILDER SHALL CONSTRUCT A TEMPORARY CROSSING PLACED OVER THE FOOTPATH.
 □ ALL PRACTICABLE MEASURES SHALL BE IMPLEMENTED TO MINIMISE WASTE TO LANDFILL. THE BUILDER MAY USE A CONSTRUCTION WASTE RECOVERY SERVICE, OR SORT AND TRANSPORT RECYCLABLE MATERIALS TO THE APPROPRIATE REGISTERED RECYCLER. MATERIALS SHALL NOT BE BURNED ON SITE.
 □ A SITE MANAGEMENT PLAN SHALL BE IMPLEMENTED FROM THE COMMENCEMENT OF WORKS, TO CONTROL SEDIMENT RUN-OFF IN ACCORDANCE WITH [INSERT RELEVANT STATE/COUNCIL GUIDELINES OR REGULATION]. SILT FENCES SHALL BE PROVIDED TO THE LOW SIDE OF THE ALLOTMENT AND AROUND ALL SOIL STOCKPILES AND STORM WATER INLET PITS/SUMPS AND 'SILT STOP' FILTER BAGS OR EQUIVALENT SHALL BE PLACED OVER ALL STORM WATER ENTRY PITS. EROSION CONTROL FABRIC SHALL BE PLACED OVER GARDEN BEDS TO PREVENT SURFACE EROSION.
 □ DUST-CREATING MATERIAL SHALL BE KEPT SPRAYED WITH WATER SO AS TO PREVENT ANY NUISANCE FROM DUST.
 □ WASTE MATERIALS SHALL NOT BE PLACED IN ANY STREET, ROAD OR RIGHT OF WAY.
 □ EARTHWORKS (UNRETAINED) SHALL NOT EXCEED 2M.
 □ CUT AND FILL BATTERS SHALL COMPLY WITH BCA TABLE 3.2.1.

PROTECTION OF THE BUILDING FABRIC
 □ THE BUILDER SHALL TAKE ALL STEPS NECESSARY TO ENSURE THE STABILITY AND GENERAL WATER TIGHTNESS OF ALL NEW AND/OR EXISTING STRUCTURES DURING ALL WORKS.
 □ WINDOWS, DOORS AND SERVICE PENETRATIONS SHALL BE FLASHED ALL AROUND.
 □ ALL PLIABLE MEMBRANES SHALL BE INSTALLED TO COMPLY AND BE IN ACCORDANCE WITH BCA 10.8.1
 □ GUTTERS AND DRAINAGE SHALL BE SUPPLIED AND INSTALLED IN ACCORDANCE WITH AS3500.3.
 □ ANTI-PONDING DEVICES/BOARDS SHALL BE INSTALLED ACCORDING TO BCA 7.3.5.
 □ DAMPCOURSES WITH WEEPHOLES AND CAVITY FLASHINGS SHALL BE INSTALLED IN ACCORDANCE WITH AS4773.2.
 □ SURFACES AROUND THE PERIMETER OF A RESIDENTIAL SLAB SHALL FALL AWAY FROM THAT SLAB BY NOT LESS THAN 50MM OVER THE FIRST 1M. WHERE NOT STIPULATED IN THE GEOTECHNICAL REPORT, FREEBOARD SHALL BE NOT LESS THAN 50MM FROM AN IMPERMEABLE SURFACE OR 150MM FROM A PERMEABLE SURFACE.
 □ SUBFLOOR VENTS SHALL BE LOCATED >600MM FROM CORNERS AND BE INSTALLED BELOW BEARERS. SUCH VENTS SHALL PROVIDE A RATE PER 1000MM RUN OF EXTERNAL OR INTERNAL CROSS WALLS OF:
 7,500MM 2 CLEAR VENTILATION WHERE PARTICLE BOARD FLOORING IS USED; OR
 6,000MM 2 FOR OTHER SUBFLOOR TYPES.
 □ [WHERE A BUILDING OTHER THAN DETACHED CLASS 10 IS LOCATED IN A TERMITE-PRONE AREA] THE BUILDING SHALL BE PROVIDED WITH A TERMITE MANAGEMENT SYSTEM COMPLIANT WITH AS3660.1 OR AS3660.2.
 □ IN SALINE OR INDUSTRIAL ENVIRONMENTS, MASONRY UNITS, MORTAR, AND ALL BUILT-IN COMPONENTS SHALL COMPLY WITH THE DURABILITY REQUIREMENTS OF TABLE 4.1 OF AS4773.1, PART 1: DESIGN.

BUSHFIRE ATTACK LEVEL	
B.A.L.-LOW	
	NO SPECIAL CONSTRUCTION REQUIREMENTS
B.A.L.-12.5	
SUBFLOOR SUPPORTS	NO SPECIAL CONSTRUCTION REQUIREMENTS
FLOORS	NO SPECIAL CONSTRUCTION REQUIREMENTS
EXTERNAL WALLS	EXTERNAL WALLS - PARTS LESS THAN 400mm ABOVE GROUND OR DECKS ECT. TO BE OF NON-COMBUSTABLE MATERIAL, 6mm FIBRE CEMENT CLAD OR BUSHFIRE RESISTANT / NATURALLY FIRE RESISTANT TIMBER
EXTERNAL WINDOWS	PROTECTED BY BUSHFIRE SHUTTER, COMPLETELY SCREENED WITH STEEL, BRONZE OR ALUMINIUM MESH OR 4mm GRADE A SAFETY GLASS OR GLASS BLOCKS WITHIN 400mm OF GROUND, DECK ECT. OPENABLE PORTION METAL SCREENED WITH FRAME OF METAL OR METAL REINFORCED PVC-U OR BUSHFIRE RESISTANT TIMBER
EXTERNAL DOORS	PROTECTED BY BUSHFIRE SHUTTER, OR SCREENED WITH STEEL, BRONZE OR ALUMINIUM MESH OR GLAZED WITH 5mm TOUGHENED GLASS, NON-COMBUSTABLE OR 35mm SOLID TIMBER FOR 400mm ABOVE THRESHOLD, METAL OR NATURALLY FIRE RESISTANT (HIGH DENSITY) TIMBER FRAMED FOR 400mm ABOVE GROUND, DECKING, ECT. TIGHT FITTING WITH WEATHER STRIP AT BASE. NYLON SEALS TO GARAGE DOORS MAX. 3mm GAP
ROOFS	NON-COMBUSTABLE COVERING. ROOF / WALL JUNCTION SEALED. OPENING FITTED WITH NON-COMBUSTABLE EMBER GUARDS. ROOF TO BE FULLY SARKED
VERANDAS, DECKS ECT.	ENCLOSED SUB FLOOR SPACE - NO SPECIAL REQUIREMENTS FOR MATERIALS EXCEPT WITHIN 400mm OF GROUND.

29. **SIX STAR ENERGY NOTES**
 * CEILING INSULATION :- R
 * EXTERNAL WALLS INSULATION :- R
 * GARAGE INTERNAL WALLS INSULATION :- R
 * DOOR SEALS TO ALL EXTERNAL HINGED DOORS AND GARAGE INTERNAL DOOR
 * TAPING OF WALL WRAP JOINTS AND JUNCTIONS WITH WINDOWS AND DOORS
 * SELF SEALING EXHAUST FANS
 * WEATHER STRIP TO EXTERNAL DOORS AND GARAGE INTERNAL DOOR
 * WATER TANK CONNECTED TO W.C.'S
 * SEALED DOWNLIGHTS

WIND SPEED :- N 1
 BUSHFIRE ATTACK LEVEL:- B.A.L. N/A
 SOIL CLASSIFICATION "P"
 REFER TO HARDCORE GEOTECH. P/L
 REPORT NO. :- 240567 (27/5/2024)
 BRICKWORK CONTROL JOINTS
 CONTROL JOINTS TO BE SPACED AT A MAX OF 5.0M
 AS PER CN9 AND CEMENT AND CONCRETE ASSOC. NOTE TN61

MELWAY REF:- .

AMENDMENTS		
ISSUE	DATE	DESCRIPTION
B	15/7/24	REVISED PLAN
C	13/8/24	DESIGN CHANGES AND SOIL ADDED
D	23/8/24	AMENDMENTS
E	8/10/24	FINAL PLANS
F	24/10/24	SLAB OVERLAY ADDED
G	6/2/24	AHD LEVELS/PLANNING/FENCING DETAILS

BONDI 161 MOD
 DATE :- / /
 SIGNED BUILDER
 SIGNED OWNER



WRITTEN DIMENSIONS TAKE PRECEDENCE OVER SCALE CONTRACTORS ARE TO CHECK ALL DIMENSIONS & LEVELS PRIOR TO COMMENCEMENT
 COPYWRITE-THIS DRAWING BELONGS THE PROPERTY OF FRENKEN HOMES
 This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

PROPOSED :- BRICK VENEER RESIDENCE
 FOR :-
 LOCATION:- LOT 210 MONTERAY WAY PAKENHAM
 DATE:- 28/4/2024
 SHEET No.:- 1
 B.P. No.:- DBU-46723
 DRG. No.:- AC24-254
 ISSUE
 G

- ☐ BUILDING TIE-DOWNS SHALL BE APPROPRIATE FOR THE SITE WIND CLASSIFICATION AND PROVIDED IN ACCORDANCE WITH BCA 5.6.6.
- ☐ CORROSION PROTECTION SHALL BE SUITED TO THE SITE CONTEXT AND PROVIDED FOR BUILT-IN STRUCTURAL STEEL MEMBERS SUCH AS STEEL LINTELS, SHELF ANGLES, CONNECTORS, ACCESSORIES (OTHER THAN WALL TIES) IN ACCORDANCE WITH TABLE 4.1 OF AS4773.1 MASONRY IN SMALL BUILDINGS, PART 1: DESIGN.
- ☐ SHEET ROOFING SHALL BE PROTECTED FROM CORROSION IN A MANNER APPROPRIATE TO THE SITE CONTEXT, IN ACCORDANCE WITH BCA TABLE 7.2.2A.
- ☐ SINGLE LEAF MASONRY WALLS SHALL BE WEATHERPROOFED PER BCA 5.7.6.
- ☐ [IN CLIMATE ZONES 6, 7 AND 8] UNLESS EXCLUDED BY BCA 10.8.3(2) ROOFS SHALL BE PROVIDED WITH VENTILATION OPENINGS PER BCA 10.8.3.
- ☐ EXTERNAL WATERPROOFING FOR ON FLAT ROOFS, ROOF TERRACES, BALCONIES AND TERRACES AND OTHER SIMILAR HORIZONTAL SURFACES LOCATED ABOVE INTERNAL SPACES OF A BUILDING SHALL COMPLY WITH BCA H2D8.
- ☐ WATERPROOFING OF WET AREAS - BEING BATHROOMS, SHOWERS, SHOWER ROOMS, LAUNDRIES, SANITARY COMPARTMENTS AND THE LIKE - SHALL BE PROVIDED IN ACCORDANCE WITH BCA 10.2.
- ☐ BALCONY WATERPROOFING SHALL BE INSTALLED IN ACCORDANCE WITH AS4654.1 & AS4654.2. GLAZING
- ☐ GLAZED UNITS SHALL BE INSTALLED IN ACCORDANCE WITH BCA8.3.2.
- ☐ FULLY FRAMED GLAZING INSTALLED IN THE PERIMETER OF BUILDINGS SHALL COMPLY WITH BCA 8.3.3.
- ☐ GLASS – INCLUDING, BUT NOT LIMITED TO, WINDOWS, DOORS, SCREENS, PANELS, SPLASHBACKS AND BARRIERS – SHALL COMPLY WITH BCA 3.3.3.
- ☐ GLAZING SUBJECT TO HUMAN IMPACT SHALL COMPLY WITH BCA 8.4. FOOTINGS
- ☐ FOOTINGS SHALL NOT, UNDER ANY CIRCUMSTANCE, ENCROACH OVER TITLE BOUNDARIES OR EASEMENT LINES.
- ☐ WHERE CONCRETE STUMPS ARE TO BE USED, THESE SHALL BE:
 - 100 X 100MM (1X 5MM HD WIRE) IF UP TO 1400MM LONG
 - 100 X 100MM (2X 5MM HD WIRES) IF 1401MM TO 1800MM LONG
 - 125 X 125MM (2X 5MM HD WIRES) IF 1801MM TO 3000MM LONG.
- ☐ 100MM X 100MM STUMPS THAT EXCEED 1200MM ABOVE GROUND LEVEL SHALL BE BRACED WHERE NO PERIMETER BASE BRICKWORK IS PROVIDED.
- ☐ ALL CONCRETE FOOTINGS SHALL BE FOUNDED AT A DEPTH TO A MINIMUM REQUIRED BEARING CAPACITY AND/OR IN ACCORDANCE WITH RECOMMENDATIONS CONTAINED IN SOIL REPORT (OR OTHERWISE AT ENGINEER'S DISCRETION). STORMWATER AND SEWERS
- ☐ [INSERT] MM DIA. CLASS 6 UPVC STORMWATER LINE MIN GRADE 1:100 SHALL BE CONNECTED TO THE LEGAL POINT OF DISCHARGE TO THE RELEVANT AUTHORITY'S APPROVAL. PROVIDE INSPECTION OPENINGS AT 9M CENTRES AND AT EACH CHANGE OF DIRECTION.
- ☐ COVERS TO UNDERGROUND STORMWATER DRAINS SHALL BE NOT LESS THAN:
 - 100MM UNDER SOIL
 - 50MM UNDER PAVED OR CONCRETE AREAS
 - 100MM UNDER UNREINFORCED CONCRETE OR PAVED DRIVEWAYS
 - 75MM UNDER REINFORCED CONCRETE DRIVEWAYS
- ☐ THE BUILDER AND SUBCONTRACTOR SHALL ENSURE THAT ALL STORMWATER DRAINS, SEWER PIPES AND THE LIKE ARE LOCATED AT A SUFFICIENT DISTANCE FROM ANY BUILDINGS, FOOTING AND/OR SLAB EDGE BEAMS SO AS TO PREVENT GENERAL MOISTURE PENETRATION, DAMPNES, WEAKENING AND UNDERMINING OF ANY BUILDING AND ITS FOOTING SYSTEM.

- SAFETY OF BUILDING USERS
- ☐ WHERE STAIRS, RAMPS AND BALUSTRADES ARE TO BE CONSTRUCTED, THESE SHALL COMPLY WITH ALL PROVISIONS OF BCA 11.2.
 - ☐ OTHER THAN SPIRAL STAIRS:
 - RISERS SHALL BE 190MM MAX AND 115MM MIN
 - GOINGS SHALL BE 355MM MAX AND 240MM MIN
 - 2R+G SHALL BE 700MM MAX AND 550MM MIN
 - THERE SHALL BE LESS THAN 125MM GAP BETWEEN OPEN TREADS.
 - ☐ ALL TREADS, LANDINGS AND THE LIKE SHALL HAVE A SLIP RESISTANCE CLASSIFICATION OF P3 OR R10 FOR DRY SURFACE CONDITIONS AND P4 OR R11 FOR WET SURFACE CONDITIONS, OR A NOSING STRIP WITH A SLIP-RESISTANCE CLASSIFICATION OF P3 FOR DRY SURFACE CONDITIONS AND P4 FOR WET SURFACE CONDITIONS.
 - ☐ BARRIERS SHALL BE PROVIDED WHERE IT IS POSSIBLE TO FALL 1M OR MORE FROM THE LEVEL OF THE TRAFFICABLE SURFACE TO THE SURFACE BENEATH. SUCH BARRIERS (OTHER THAN TENSIONED WIRE BARRIERS) SHALL BE:
 - 1000MM MIN ABOVE FINISHED STAIR LEVEL (FSL) OF BALCONIES, LANDINGS ETC; AND
 - 865MM MIN ABOVE FSL OF STAIR NOSING OR RAMP; AND
 - VERTICAL, WITH GAPS OF NO MORE THAN 125MM.
 - ☐ WHERE THE FLOOR BELOW A BEDROOM WINDOW IS 2M OR MORE ABOVE THE SURFACE BENEATH, THE WINDOW SHALL COMPLY WITH BCA CLAUSE 11.3.7.
 - ☐ WHERE THE FLOOR BELOW A WINDOW OTHER THAN IN A BEDROOM IS 4M OR MORE ABOVE THE SURFACE BENEATH, THE WINDOW SHALL COMPLY WITH BCA CLAUSE 11.3.8.
 - ☐ WHERE A BEDROOM WINDOW IS 2M OR MORE ABOVE THE SURFACE BENEATH, OR IT IS POSSIBLE TO FALL 4M OR MORE FROM THE LEVEL OF ANY TRAFFICABLE SURFACE TO THE SURFACE BENEATH, ANY HORIZONTAL ELEMENT WITHIN A BARRIER BETWEEN 150MM AND 760MM ABOVE THE FLOOR SHALL NOT FACILITATE CLIMBING.
 - ☐ HANDRAILS SHALL BE CONTINUOUS, WITH TOPS SET >865MM VERTICALLY ABOVE STAIR NOSING AND FLOOR SURFACE OF RAMPS.
 - ☐ WIRE BARRIERS SHALL COMPLY WITH BCA 11.3.4 AND 11.3.6.
 - ☐ A GLASS BARRIER OR WINDOW SERVING AS A BARRIER SHALL COMPLY WITH BCA H1D8.
 - ☐ CLASS 1 BUILDINGS WITH AIR PERMEABILITY OF NOT MORE THAN 5 M³ /HR.M² AT 50 PA SHALL BE PROVIDED WITH A MECHANICAL VENTILATION SYSTEM COMPLYING WITH H6V3. INWARD-OPENING SWING DOORS TO FULLY ENCLOSED SANITARY COMPARTMENTS SHALL COMPLY WITH BCA CLAUSE 10.4.2.
 - ☐ ALL SHOWER WALLS AND WALLS ADJACENT TO TOILET SHALL BE BRACED WITH 12MM PLY FOR FUTURE GRAB RAILS OR SUPPLY NOGGINGS WITH A THICKNESS OF AT LEAST 25MM IN ACCORDANCE WITH RECOMMENDATIONS OF LIVEABLE HOUSING DESIGN GUIDELINES.
 - ☐ FLOORING IN WET AREAS, LAUNDRY AND KITCHEN SHALL BE SLIP RESISTANT.
 - ☐ DOOR HARDWARE SHALL BE INSTALLED 900MM – 1100MM ABOVE THE FINISHED FLOOR.
 - ☐ THERE SHALL BE A LEVEL TRANSITION BETWEEN ABUTTING INTERNAL SURFACES (A MAXIMUM VERTICAL TOLERANCE OF 5MM BETWEEN ABUTTING SURFACES IS ALLOWABLE PROVIDED THE LIP IS ROUNDED OR BEVELLED).

- SERVICES
- ☐ SOLAR COLLECTOR PANEL LOCATIONS ARE INDICATIVE ONLY. LOCATION AND SIZE ARE DEPENDENT ON MANUFACTURER'S/INSTALLER'S RECOMMENDATION.
 - ☐ DUCTWORK FOR HEATING AND COOLING SYSTEMS SHALL COMPLY WITH AS4254 & AS/NZS 4859.1 IN ACCORDANCE WITH CLIMATE ZONE REQUIREMENTS SET DOWN IN BCA TABLE 3. TIMBER FRAMING
 - ☐ STANDARD TIMBER ROOFING AND WALL FRAMING SHALL BE PROVIDED IN ACCORDANCE WITH AS1684 (RESIDENTIAL TIMBER-FRAMED CONSTRUCTION) AND ALL RELEVANT SUPPLEMENTS. ELECTRICAL
 - ☐ SMOKE DETECTORS SHALL BE FITTED WHERE NONE ARE PRESENT, OR WHERE EXISTING ARE NON-COMPLIANT WITH AS3786.
 - ☐ NEW SMOKE DETECTORS SHALL BE INTERCONNECTED; MAINS-POWERED; AND LOCATED AND INSTALLED PER BCA 9.5.2 AND 9.5.4.
 - ☐ IN A CLASS 10A PRIVATE GARAGE, AN ALTERNATIVE ALARM MAY BE INSTALLED PER BCA 9.5.1(B).
 - ☐ LIGHT SWITCHES SHALL BE POSITIONED IN A CONSISTENT LOCATION 900MM – 1100MM ABOVE THE FINISHED FLOOR LEVEL; HORIZONTALLY ALIGNED WITH THE DOOR HANDLE AT THE ENTRANCE TO A ROOM.
 - ☐ POWER POINTS SHALL NOT BE INSTALLED LOWER THAN 300MM ABOVE FINISHED FLOOR LEVEL.
 - ☐ ALL ELECTRICAL PENETRATIONS SHALL BE SEALED USING MATERIAL APPROPRIATE TO THE RATING OF THE CABLE AND/OR DEVICE.
 - ☐ ONLY STAMPED IC4-RATED DOWNLIGHTS SHALL BE INSTALLED AND INSULATION SHALL NOT BE PENETRATED FOR DOWNLIGHTS.
 - ☐ DUCTWORK FOR EXHAUST FANS AND HEATING AND COOLING SYSTEMS SHALL COMPLY WITH AS4254 & AS/NZS 4859.1 IN ACCORDANCE WITH CLIMATE ZONE REQUIREMENTS SET DOWN IN BCA 13.7.4.
 - ☐ EXHAUST FROM A BATHROOM, SANITARY COMPARTMENT OR LAUNDRY SHALL BE DISCHARGED DIRECTLY VIA AN INSULATED SHAFT OR R1 INSULATED DUCTING TO OUTDOOR AIR. MINIMUM FLOW RATES SHALL BE:
 - 40 L/S FOR KITCHEN & LAUNDRY
 - 25 L/S FOR BATHROOM OR SANITARY COMPARTMENT.
 - ☐ AN EXHAUST SYSTEM THAT IS NOT RUN CONTINUOUSLY AND IS SERVING A BATHROOM OR SANITARY COMPARTMENT THAT IS NOT VENTILATED IN ACCORDANCE WITH BCA 10.6.2(A) SHALL BE INTERLOCKED WITH THE ROOM'S LIGHT SWITCH; AND INCLUDE A 10 MINUTE RUN-ON TIMER.
 - ☐ EXHAUST FANS, RANGEHOODS AND THE LIKE SHALL BE INSTALLED WITH SELF-CLOSING DAMPERS.

- ☐ BOX GUTTERS AND MANHOLE COVERS SHALL BE INSULATED TO THE SAME R-VALUE AS THE ROOF, USING INSULATION BATTS OR BLANKET OR CLOSED-CELL FOAM.
- ☐ DOWNLIGHTS SHALL BE STAMPED AS IC4 RATED, AIRTIGHT AND COVERED BY INSULATION.
- ☐ [IN CLIMATE ZONES 6, 7 AND 8] A VAPOUR PERMEABLE LAYER SHALL BE INSTALLED PER MANUFACTURER'S INSTRUCTIONS IN ALL NEW EXTERNAL WALLS. THE MATERIAL SHALL BE OVERLAPPED AND FULLY TAPED ON THE EXTERNAL SIDE TO ENSURE A TIGHT SEAL. ALL PENETRATIONS IN THE MEMBRANE SHALL BE SEALED, ENSURING THAT THE MATERIAL COVERS GAPS BETWEEN STUDS AND DOORS AND WINDOW FRAMES. ANY FLASHING AROUND WINDOWS SHALL BE TAPED OVER THE BUILDING WRAP.
- ☐ WHERE A FOIL-BACKED MEMBRANE IS USED, TIMBER BATTENS SHALL BE USED TO MINIMISE THERMAL CONDUCTION.
- ☐ ALL TRADES SHALL BE INSTRUCTED TO REPLACE ANY INSULATION THEY HAVE REMOVED IN THE COURSE OF THEIR WORK AND TO TAPE ANY CUTS/PENETRATIONS IN BUILDING WRAP. ALL PENETRATIONS SHALL BE CAULKED USING A FIT-FOR-PURPOSE FLEXIBLE SEALANT.
- ☐ ALL REDUNDANT OPENINGS SUCH AS DECOMMISSIONED CHIMNEYS AND WALL VENTS SHALL BE SEALED OFF AT TOP AND BOTTOM, UNLESS AN UNFLUED GAS HEATER IS PRESENT.
- ☐ CAULKING PRODUCTS SHALL BE APPROPRIATE FOR THE INTENDED APPLICATION.
- ☐ BEFORE INSTALLING MOULDINGS, A FIT-FOR-PURPOSE, LONG-LASTING PROPRIETARY TAPE OR FLEXIBLE CAULKING PRODUCT SHALL BE USED TO SEAL JUNCTIONS OF:
 - PLASTERBOARD AND FLOOR
 - PLASTERBOARD AND TOP PLATE (FOR SQUARE SET CORNICES)
 - VERTICAL AND HORIZONTAL PLASTERBOARD
 - TOPS, BOTTOMS AND SIDES OF ARCHITRAVES AND PLASTERBOARD.
 - ALL EXHAUST FANS AND DUCTS, INCLUDING RANGEHOODS, SHALL BE FITTED WITH SELF-CLOSING MECHANISMS.
- ☐ WHERE IT IS NOT POSSIBLE TO INSULATE UNDER AN EXISTING TIMBER FLOOR, GAPS BETWEEN FLOORBOARDS SHALL BE SEALED BEFORE APPLYING FINISHES OR COVERINGS.
- ☐ EXTERNAL DOORS AND WINDOWS SHALL BE DRAUGHTPROOFED PER BCA 13.4.4 USING A DURABLE, FIT-FOR-PURPOSE SEAL.
- ☐ CAVITY SLIDER POCKETS SHALL BE SEALED BEFORE INSTALLATION, EITHER BY WRAPPING WITH VAPOUR PERMEABLE MEMBRANE, OR BY SCREWING PLASTER SECURELY TO THE FRAME AND APPLYING A SILICON BEAD.
- ☐ CONDITIONED CLASS 1 AND UNCONDITIONED CLASS 10A SPACES SHALL BE SEPARATED BY INSULATION. ANY OPENINGS BETWEEN SUCH SPACES SHALL BE WEATHER-STRIPPED.
- ☐ THE CLIENT RETAINS THE RIGHT TO IMPLEMENT A BLOWER DOOR TEST TO TEST FOR AIR TIGHTNESS PRIOR TO PAINTING. TARGET AIR PERMEABILITY IS NOT MORE THAN [INSERT] M³ /HR.M² AT 50 PA.
- ☐ WINDOW SIZES NOMINATED ARE NOMINAL. ACTUAL SIZE MAY VARY MINIMALLY ACCORDING TO MANUFACTURER; HOWEVER, OPENING STYLES, OVERALL SIZE, U-VALUE AND SHGC VALUES ARE INBUILT INTO THE ENERGY RATING AND MAY NOT BE ALTERED WITHOUT THE EXPRESS APPROVAL OF THE PROJECT'S ENERGY RATER.
- ☐ GLAZED DOORS AND WINDOWS SHALL BE [INSERT] WIND RATED, DOUBLE-GLAZED, WEATHER-STRIPPED AND FLASHED ALL AROUND.
- ☐ OPENABLE WINDOWS SHALL BE PROVIDED WITH FLYSCREENS.

BONDI 161 MOD

DATE :- / /
SIGNED BUILDER
SIGNED OWNER



WRITTEN DIMENSIONS TAKE PRECEDENCE OVER SCALE CONTRACTORS ARE TO CHECK ALL DIMENSIONS & LEVELS PRIOR TO COMMENCEMENT COPYWRITE-THIS DRAWING BELONGS THE PROPERTY OF FRENKEN HOMES

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

PROPOSED :- BRICK VENEER RESIDENCE
FOR :- [REDACTED]
LOCATION:- LOT 210 MONTERAY WAY PAKENHAM

DATE:- 28/4/2024	B.P. No.:- DBU-46723	ISSUE
SHEET No.:- 2	DRG. No.:- AC24-254	G

A5. RESCODE SITE COVERAGE STATISTICS	
SITE AREA	375.0 M
RESIDENCE	161.5 M
GARAGE	36.2 M
PORCH	2.9 M
ALFRESCO	9.2 M
TOTAL SITE COVER	209.8 M
SITE COVER RATIO	56% (0.559)
DRIVE WAY	25.0 M
OTHER PAVED AREAS	0.0 M
TOTAL HARD COVER	234.8 M
HARD COVER RATIO	63% (0.626)
NOTE: 20 % TO BE PERMEABLE ie NOT COVERED	


DRAINAGE REQUIREMENTS	
A/ ALL SURFACE DRAINAGE WORKS SHALL BE INSTALLED IN ACCORDANCE WITH THE ENGINEERS DESIGN DETAIL FOR THE SELECTED FOOTING SYSTEM AND SOIL CLASSIFICATION AND IN ACCORDANCE WITH CLAUSE 5.6.3. DRAINAGE REQUIREMENTS OF AS2870.2011, WHEREIN FOR BUILDINGS ON MODERATELY, HIGHLY AND REACTIVE SITES:	
- SURFACE DRAINAGE SHALL BE CONTROLLED THROUGHOUT CONSTRUCTION AND BE COMPLETED BY THE FINISH OF CONSTRUCTION	
- THE BASE OF TRENCHES SHALL SLOPE AWAY FROM THE BUILDING	
- WHERE PIPES PASS UNDER THE FOOTING SYSTEMS, CLAY PLUGS ARE ADOPTED TO PREVENT THE INGRESS OF WATER	
B/ FOR BUILDINGS ON HIGHLY AND REACTIVE SITES. THE DRAINER SHALL PROVIDE DRAINAGE ARTICULATION TO ALL STORMWATER, SANITARY PLUMBING AND DISCHARGE PIPES IN ACCORDANCE WITH CLAUSE 5.6.4. PLUMBING REQUIREMENTS, WHEREIN FLEXIBLE JOINTS IMMEDIATELY OUTSIDE THE FOOTING AND COMMENCING WITHIN 1.0M OF THE BUILDING PERIMETER ARE REQUIRED TO ACCOMMODATE THE REQUIRED DIFFERENTIAL MOVEMENT BASED ON THE SOIL CLASSIFICATION.	
C/ SURFACE WATER MUST BE DIVERTED AWAY FROM THE DWELLING AND GRADED AWAY FROM ALL FOUNDATIONS TO GIVE A SLOPE OF NOT LESS THAN 50mm OVER THE FIRST 1000mm FROM THE DWELLING.	
D/ SUBSURFACE DRAINS TO REMOVE GROUND OR TABLE WATER SHALL BE DETAILED BY THE DESIGN ENGINEER. FURTHERMORE, DAMP-PROOFING MEMBRANE IN ACCORDANCE WITH 5.3.3. SHALL BE INSTALLED FOR THE GROUNDWATER OR AGGRESSIVE SOILS.	

TBM:
ELECTRICITY PIT
R.L. 52.58

SITE PLAN
SCALE :- 1:200

LEVELS SHOWN ON THIS PLAN ARE TO THE AUSTRALIAN HEIGHT DATUM BASED ON NAR NAR GOON PM 199 (R.L.43.901)

DIMENSIONS & LEVELS TO BE VERIFIED BY CERTIFIED COPY OF TITLE OR RELOCATION SURVEY OR APPROVED PLAN OF SUB-DIVISION



EXCAVATE & FILL SITE TO R.L.: 51.91

BATTERS ARE AT 45° U.N.O.
CUT OFF DRAIN AT BASE OF EXCAVATION TO CONNECT TO S.W.D. SYSTEM VIA SILT PIT BY OWNER OR CONTRACT VARIATION

NOTE:- WING FENCE SETBACK 1500mm FROM FRONT WITH SIDE ACCESS GATE

LOT 209 VACANT SITE AS OF 24/01/25

30.00M (8°57'40")
NOTE:- 1800mm HIGH CAPPED TIMBER PALING FENCE WITH EXPOSED POSTS ON CONC. RETAINING WALL

LOT 210 SITE AREA: 375.0 M

NOTE:- FILL PADS OVER 300mm HIGH TO HAVE BATTERS AT 1:2 OR 30° MAX.

NOTE:- 110 M OF SECLUDED PRIVATE OPEN SPACE TO REAR

GARAGE FFL: 51.82

PROPOSED RESIDENCE FFL: 52.16

NOTE:- FILL TO SIDE OF HOUSE TO G.L. 51.72

NOTE:- 1800mm HIGH CAPPED TIMBER PALING FENCE WITH EXPOSED POSTS

NOTE:- RETAINING WALL UP TO 800mm HIGH FOR FILL ONLY

LOT 211 VACANT SITE AS OF 24/01/25

LOT 225 VACANT SITE AS OF 24/01/25

12.50M (98°57'40")

NOTE: 2000lt (2000x620x2020h) POLYWATER TANK WITH 50M'S OF ROOF CATCHMENT CONNECTED TO WC.'S WITH OVERFLOW TO S.W.SYSTEM


LOT 224 VACANT SITE AS OF 24/01/25

STORM WATER DRAINS: TO LEGAL POINT OF DISCHARGE TO COUNCIL REQUIREMENTS BUILDER TO VERIFY LPD PRIOR TO CONNECTION

SEWER PIPE 150mm DIA 2020mm OFFSET 3080mm DEEP

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

800 MAX. HIGH RETAINING WALL FOR FILL ONLY
SCALE :- 1:50



NOTES	
LEVELS ARE TO AN A.H.D. AND CONTOURS ARE SHOWN ARE 200mm INTERVALS	INSPECTION OPENINGS TO BE PROVIDED AT CHANGES IN DIRECTION AND FOR LENGTHS GREATER THAN 20M
CONNECT ALL DOWN PIPES TO 90mm DIA. UPVC S.W.DRAINAGE SYSTEM OR TO STORM WATER SYSTEM AS DESIGNED BY ENGINEER AND DISCHARGE TO LEGAL POINT IN ACCORDANCE WITH LOCAL COUNCIL REQUIREMENTS	RESIDENCE FINISHED FLOOR LEVEL TO BE NOT LESS THAN 150mm ABOVE FINISHED GROUND LEVEL: REFER TO SITE PLAN
	PROVIDE AGGY DRAINS CONNECTED TO SILT PITS AT BASE OF BATTERS. AGGY DRAINS CONNECTED TO STORM WATER SYSTEM VIA SILT PITS

BONDI 161 MOD

DATE :- / /
SIGNED BUILDER
SIGNED OWNER



WRITTEN DIMENSIONS TAKE PRECEDENCE OVER SCALE CONTRACTORS ARE TO CHECK ALL DIMENSIONS & LEVELS PRIOR TO COMMENCEMENT
COPYWRITE:- THIS DRAWING BELONGS THE PROPERTY OF FRENKEN HOMES

PROPOSED :- BRICK VENEER RESIDENCE		
FOR :- [REDACTED]		
LOCATION:- LOT 210 MONTERAY WAY PAKENHAM		
DATE:- 28/4/2024	B.P. No.:- DBU-46723	ISSUE
SHEET No.:- 3	DRG. No.:- AC24-254	G

A5. RESCODE SITE COVERAGE STATISTICS	
SITE AREA	375.0 M
RESIDENCE	161.5 M
GARAGE	36.2 M
PORCH	2.9 M
ALFRESCO	9.2 M
TOTAL SITE COVER	209.8 M
SITE COVER RATIO	56% (0.559)
DRIVE WAY	25.0 M
OTHER PAVED AREAS	0.0 M
TOTAL HARD COVER	234.8 M
HARD COVER RATIO	63% (0.626)
NOTE: 20 % TO BE PERMEABLE ie NOT COVERED	

DRAINAGE REQUIREMENTS	
A/ ALL SURFACE DRAINAGE WORKS SHALL BE INSTALLED IN ACCORDANCE WITH THE ENGINEERS DESIGN DETAIL FOR THE SELECTED FOOTING SYSTEM AND SOIL CLASSIFICATION AND IN ACCORDANCE WITH CLAUSE 5.6.3. DRAINAGE REQUIREMENTS OF AS2870.2011, WHEREIN FOR BUILDINGS ON MODERATELY, HIGHLY AND REACTIVE SITES:	
- SURFACE DRAINAGE SHALL BE CONTROLLED THROUGHOUT CONSTRUCTION AND BE COMPLETED BY THE FINISH OF CONSTRUCTION	
- THE BASE OF TRENCHES SHALL SLOPE AWAY FROM THE BUILDING	
- WHERE PIPES PASS UNDER THE FOOTING SYSTEMS, CLAY PLUGS ARE ADOPTED TO PREVENT THE INGRESS OF WATER	
B/ FOR BUILDINGS ON HIGHLY AND REACTIVE SITES, THE DRAINER SHALL PROVIDE DRAINAGE ARTICULATION TO ALL STORMWATER, SANITARY PLUMBING AND DISCHARGE PIPES IN ACCORDANCE WITH CLAUSE 5.6.4. PLUMBING REQUIREMENTS, WHEREIN FLEXIBLE JOINTS IMMEDIATELY OUTSIDE THE FOOTING AND COMMENCING WITHIN 1.0M OF THE BUILDING PERIMETER ARE REQUIRED TO ACCOMMODATE THE REQUIRED DIFFERENTIAL MOVEMENT BASED ON THE SOIL CLASSIFICATION.	
C/ SURFACE WATER MUST BE DIVERTED AWAY FROM THE DWELLING AND GRADED AWAY FROM ALL FOUNDATIONS TO GIVE A SLOPE OF NOT LESS THAN 50mm OVER THE FIRST 1000mm FROM THE DWELLING.	
D/ SUBSURFACE DRAINS TO REMOVE GROUND OR TABLE WATER SHALL BE DETAILED BY THE DESIGN ENGINEER. FURTHERMORE, DAMP-PROOFING MEMBRANE IN ACCORDANCE WITH 5.3.3. SHALL BE INSTALLED FOR THE GROUNDWATER OR AGGRESSIVE SOILS.	

TBM:
ELECTRICITY PIT
R.L. 52.58

MONTEREY WAY


cut
Fill

SITE PLAN
SCALE :- 1:200


LEVELS SHOWN ON THIS PLAN ARE TO THE AUSTRALIAN HEIGHT DATUM BASED ON NAR NAR GOON PM 199 (R.L.43.901)

DIMENSIONS & LEVELS TO BE VERIFIED BY CERTIFIED COPY OF TITLE OR RELOCATION SURVEY OR APPROVED PLAN OF SUB-DIVISION

EXCAVATE & FILL SITE TO R.L.: 51.91
BATTERS ARE AT 45° U.N.O.
CUT OFF DRAIN AT BASE OF EXCAVATION TO CONNECT TO S.W.D. SYSTEM VIA SILT PIT BY OWNER OR CONTRACT VARIATION



800 MAX. HIGH RETAINING WALL FOR FILL ONLY
SCALE :- 1:50



LOT 225
VACANT SITE
AS OF 24/01/25

NOTE: 2000lt (2000x620x2020h) POLYWATER TANK WITH 50M'S OF ROOF CATCHMENT CONNECTED TO WC'S WITH OVERFLOW TO S.W.SYSTEM


STORM WATER DRAINS: TO LEGAL POINT OF DISCHARGE TO COUNCIL REQUIREMENTS BUILDER TO VERIFY LPD PRIOR TO CONNECTION

SEWER PIPE
150mm DIA
2020mm OFFSET
3080mm DEEP

LOT 224
VACANT SITE
AS OF 24/01/25

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

NOTES	
LEVELS ARE TO AN A.H.D. AND CONTOURS ARE SHOWN ARE 200mm INTERVALS	INSPECTION OPENINGS TO BE PROVIDED AT CHANGES IN DIRECTION AND FOR LENGTHS GREATER THAN 20M
CONNECT ALL DOWN PIPES TO 90mm DIA. UPVC S.W.DRAINAGE SYSTEM OR TO STORM WATER SYSTEM AS DESIGNED BY ENGINEER AND DISCHARGE TO LEGAL POINT IN ACCORDANCE WITH LOCAL COUNCIL REQUIREMENTS	RESIDENCE FINISHED FLOOR LEVEL TO BE NOT LESS THAN 150mm ABOVE FINISHED GROUND LEVEL: REFER TO SITE PLAN
	PROVIDE AGGY DRAINS CONNECTED TO SILT PITS AT BASE OF BATTERS. AGGY DRAINS CONNECTED TO STORM WATER SYSTEM VIA SILT PITS



BONDI 161 MOD



DATE :- / /
SIGNED BUILDER
SIGNED OWNER



WRITTEN DIMENSIONS TAKE PRECEDENCE OVER SCALE CONTRACTORS ARE TO CHECK ALL DIMENSIONS & LEVELS PRIOR TO COMMENCEMENT
COPYWRITE:-THIS DRAWING BELONGS THE PROPERTY OF FRENKEN HOMES

PROPOSED :- BRICK VENEER RESIDENCE
FOR :-
LOCATION:- LOT 210 MONTEREY WAY PAKENHAM


DATE:- 28/4/2024	B.P. No.:- DBU-46723	ISSUE
SHEET No.:- 3	DRG. No.:- AC24-254	G



LOCALLY FILL AROUND DOORWAYS TO AVOID THE NEED FOR STEPS AND GRADE SOIL AWAY FROM HOUSE AS REQUIRED



WC DOORS TO OPEN OUT OR HAVE REMOVABLE HINGES IF WC HAS LESS THAN 1200mm OF CLEARANCE FROM DOOR TO CLOSET PAN

NOTE: 2000lt (2000x620x2020h) POLYWATER TANK WITH 50M'S OF ROOF CATCHMENT CONNECTED TO W.C.'S WITH OVERFLOW TO S.W. SYSTEM



350x350 BRICK PIERS ON CONCRETE PAD REFER TO ENGINEERS DESIGN FOUNDED AS PER SOIL REPORT



100x100x6t GALVANIZED STEEL LINTEL WITH 115mm MIN. END BEARING TO SIDE OF PORCH ONLY



This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

FLOOR PLAN

SCALE :- 1:100
AREA STATISTICS
FLOOR PLAN 161.5 M
GARAGE 36.2 M
PORCH 2.9 M
ALFRESCO 9.2 M



ELEVATION

BONDI 161 MOD
DATE :- / /
SIGNED BUILDER
SIGNED OWNER




WRITTEN DIMENSIONS TAKE PRECEDENCE OVER SCALE CONTRACTORS ARE TO CHECK ALL DIMENSIONS & LEVELS PRIOR TO COMMENCEMENT
COPYWRITE:- THIS DRAWING BELONGS THE PROPERTY OF FRENKEN HOMES

PROPOSED :- BRICK VENEER RESIDENCE		
FOR :-		
LOCATION:- LOT 210 MONTERAY WAY PAKENHAM		
DATE:- 28/4/2024	B.P. No:- DBU-46723	ISSUE
SHEET No:- 4	DRG. No:- AC24-254	G

SETOUT PLAN TO BE READ IN CONJUNCTION WITH FLOOR PLAN. BUILDER TO VERIFY DIMENSIONS ARE CORRECT PRIOR TO COMMENCEMENT OF WORKS

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.



SETOUT PLAN
SCALE :- 1:100

BONDI 161 MOD

DATE :- / /
SIGNED BUILDER
SIGNED OWNER




WRITTEN DIMENSIONS TAKE PRECEDENCE OVER SCALE CONTRACTORS ARE TO CHECK ALL DIMENSIONS & LEVELS PRIOR TO COMMENCEMENT

COPYWRITE:-THIS DRAWING BELONGS THE PROPERTY OF FRENKEN HOMES

PROPOSED :- BRICK VENEER RESIDENCE
FOR :-
LOCATION:- LOT 210 MONTERAY WAY PAKENHAM


DATE:- 28/4/2024	B.P. No.:- DBU-46723	ISSUE
SHEET No.:- 5	DRG. No.:- AC24-254	G

BRICKS – AUSTRAL - BISCOTTI



NOTE:- BRICKWORK OVER WINDOWS AND DOORS WITH CAVITY FLASHING TO WEEP HOLES

NOTE:- CEMENT TILE ROOF AT 22.5° PITCH



ELEVATION C
SCALE :- 1:100
EAST ELEVATION

DOWNPIPE TO GARAGE SHALE GREY



DOWNPIPE BALANCE - JASPER



RENDER TO GARAGE – BASALT



ROOF TILES – BRISTLE – LATE MIST CLASSIC




WINDOWS & METERBOX – JASPER



FASCIA & GUTTER – BASALT



ELEVATION A
SCALE :- 1:100
WEST ELEVATION



LETTERBOX – BASALT



GARAGE DOOR COLOUR – SHALE GREY



FRONT DOOR COLOUR – SHALE GREY



5480
OVERALL RIDGE HEIGHT FROM NATURAL GROUND


NOTE: ALUMINIUM ARMADALE AWNING WINDOWS TO FRONT ELEVATION ONLY

NOTE:- CEMENT TILE ROOF AT 22.5° PITCH


NOTE: SELECTED RENDER FINISH TO GARAGE WITH RETURNS TO SIDES

NOTE:- ALUMINIUM AWNING AND SLIDING WINDOWS TO SIDE AND REAR ELEVATIONS AS SHOWN

NOTE:- CEMENT TILE ROOF AT 22.5° PITCH



ELEVATION B
SCALE :- 1:100
NORTH ELEVATION



ELEVATION D
SCALE :- 1:100
SOUTH ELEVATION


920DF 2340H
2300 X 4800 PANEL LIFT DOOR REFER TO PROJECT SPEC.
NOTE: SELECTED STACKING STONE FINISH TO PORCH

TILES TO PIERS – NCIFN10002Z



SAFETY GLAZING TO A.S.1288 REFER TO GENERAL NOTES

820DF DRIVEWAY – COLOUR THROUGH CONCRETE - BLUESTONE



BONDI 161 MOD

DATE :- / /

SIGNED BUILDER

SIGNED OWNER



WRITTEN DIMENSIONS TAKE PRECEDENCE OVER SCALE CONTRACTORS ARE TO CHECK ALL DIMENSIONS & LEVELS PRIOR TO COMMENCEMENT

COPYWRITE:-THIS DRAWING BELONGS THE PROPERTY OF FRENKEN HOMES

This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.

PROPOSED :- BRICK VENEER RESIDENCE FOR :-

LOCATION:- LOT 210 MONTERAY WAY PAKENHAM

DATE:- 28/4/2024

B.P. No.:- DBU-46723

ISSUE


SHEET No.:- 6

DRG. No.:- AC24-254

G

FENCING ELEVATIONS

SCALE :- 1:100




ELEVATION C

SCALE :- 1:100
EAST ELEVATION

NOTE:- 1800mm HIGH CAPPED TIMBER PALING FENCE WITH EXPOSED POSTS ON TOP OF EXISTING RETAINING WALL AND STEPPED WITH WALL


This copied document is made available for the purpose of the planning process as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited.



ELEVATION A

SCALE :- 1:100
WEST ELEVATION


NOTE:- 1800mm HIGH CAPPED TIMBER PALING FENCE WITH EXPOSED POSTS STEPPED WITH GROUNDLINE



ELEVATION B

SCALE :- 1:100
NORTH ELEVATION

NOTE:- 1800H WING FENCE SETBACK 1500mm FROM FRONT WITH SIDE ACCESS GATE BUILT TO MATCH SIDE FENCE



ELEVATION D

SCALE :- 1:100
SOUTH ELEVATION

NOTE:- 1800mm HIGH CAPPED TIMBER PALING FENCE WITH EXPOSED POSTS ON TOP OF EXISTING RETAINING WALL AND STEPPED WITH WALL

BONDI 161 MOD

DATE :- / /

SIGNED BUILDER

SIGNED OWNER



WRITTEN DIMENSIONS TAKE PRECEDENCE OVER SCALE CONTRACTORS ARE TO CHECK ALL DIMENSIONS & LEVELS PRIOR TO COMMENCEMENT

COPYWRITE:-THIS DRAWING BELONGS THE PROPERTY OF FRENKEN HOMES

PROPOSED :- BRICK VENEER RESIDENCE

FOR :-

LOCATION:- LOT 210 MONTEREY WAY PAKENHAM

DATE:- 28/4/2024

B.P. No.:- DBU-46723

ISSUE

SHEET No.:- 6.1

DRG. No.:- AC24-254

H

