DRAWING REGISTER

TP00 COVER PAGE
TP01 SITE CONTEXT
TP02 SITE SURVEY

TP03 SITE PLAN, GROUND FLOOR OVERALL

TP04 GROUND FLOOR PLAN

TP05 FIRST FLOOR PLAN

TP06 NORTH AND EAST ELEVATIONS


TP07 NORTH STREETSCAPE, MASSING AND FENCE

TP08 SHADOW STUDY 9,12 AND 3PM

TP09 ARTIST IMPRESSIONS

TP10 SHADOW STUDY 10,11,1pm AND 2pm

TP11 BUILDING CONCEPT SIGNAGE





	DESIGN:	REV 2	SCALE: NS @ A1
	DRAWN:	CJV	SHEET No: CHILDCARE_TP_00
F	PROJECT No:	211030	DATE: JULY 2022

	ISSUE:	DATE:	REVISION:	\
	APPLICATION FOR A PLANNING PERMIT	01.09.2022	1	
	RESPONSE TO COUNCIL RFI	27.03.2023	2	
7				/ (

MONOMEATH PAKENHAM	COVER PAGE	
24-26 HONEYEATER WAY PAKENHAM, VIC 3810		TP00



RESPONSE TO COUNCIL RFI

CHILDCARE_TP_01

JULY 2022

211030

27.03.2023


24-26 HONEYEATER WAY


PAKENHAM, VIC 3810


Town Planning Committee Meeting 2 September 2024


3

TP01













ATTACHMENT 5.1.3









as set out in the Planning and Environment Act 1987. The information must not be used for any other purpose. By taking a copy of this document you acknowledge and agree that you will only use the document for the purpose specified above and that any dissemination, distribution or copying of this document is strictly prohibited. WAY WEBSTER 800mm LANDSCAPING BUFFER TO PROPOSED FENCE LINE The state of the s MYN (50) TO FUTURE DETAIL — 800mm LANDSCAPING \ BUFFER TO PROPOSED BA (12) CPB (15) UP (1) KP (18) PLAY AREA 1 12 CHILDREN 43.0 M2 (1 child per 3.5m2) PLAY AREA 2 18 CHILDREN 64.0 M2 GROUND FLOOR CPB (15) 50 KIDS, AREA 300m2 <u>TL (^1,)</u> ____ EXISTING CROSSOVER PLAY AREA 3 TO BE RMOVED 20 CHILDREN PORCH SLEEP ROOM 800mm LANDSCAPING BUFFER TO PROPOSED BIN ENCLOSURE 3.0m X 4.7m PAT (12) CONCRETE FOOTPATI RL: 25.41 A.H.D. PROPOSED CROSSOVER No. SPACES, RATE 0.22 PER CHILD Proposed deciduous trees Existing trees to be retained Play area to future details Proposed concrete areas


Surface Finishes Detail

Garden Beds




75mm ORGANIC PINE BARK MULCH 400mm APPROVED MEDIUM LOAM SOIL MIN 150mm DEEP ROTARY HOED SUBGRADE

Shrub Planting




Advanced Tree Planting



Plant Schedule

	BOTANICAL NAME	COMMON NAME	QTY	SUPPLY SIZE	MATURE H x V
TREES					
AFB	Agonis flexuosa 'Burgundy	Willow Myrtle	4	40ltr / min 1.8m high	5m x 3m
HF	Hymenosporum flavum	Native Frangipani	4	40ltr / min 1.8m high	10m x 4m
LIN	Lagerstroemia indica 'Natchez'	White Crepe Myrtle	1	40ltr / min 1.8m high	8m x 6m
LIS	Lagerstroemia indica 'Sioux'	Crepe Myrtle	1	40ltr / min 1.8m high	4.5m x 3m
LIT	Lagerstroemia indica x L.fauriei 'Tuscarora'	Crepe Myrtle	1	40ltr / min 1.8m high	4.5m x 5m
TL	Tristaniopsis laurina	Kanooka	1	40ltr / min 1.8m high	7m x 5m
TLU	Tristaniopsis Laurina' Luscious'	Water Gum	2	40ltr / min 1.8m high	12m x 5m
UP	Ulmus parvifolia	Chinese Elm	1	40ltr / min 1.8m high	10m x 10m
SHRUBS	3				
AS	Acmena smithii var. 'Minor'	Compact Lilly Pilly	11	20cm pot	3m x 1.5m
IA	Indigofera australis	Austral Indigo	2	20cm pot	1.5m x 1.2m
NDM	Nandina Domestica 'Magical lemon lime'	Heavenly bamboo 'Lemon-Lime'	9	20cm pot	.9m x .8m
RI	Rhapiolepis indica	Indian Hawthorn	2	20cm pot	1.5m x 1m
SASF	Syzygium australe 'Select Form'	Select Form Lilly Pilly	3	20cm pot	3 x 1.2m (clippe
GROUNI	D COVERS & LOW SHRUBS				
ВА	Brachyscome multifida	Cut-Leaf Daisy	26	14cm pot	.3m x .75m
CHR	Chrysocephalum apiculatum	Yellow Buttons	28	14cm pot	.5m x .7m
	Carpobrotus rossii	Native Pig Face	30	14cm pot	.2m x 1.2m
CPB		•			
CPB KP	Kennedia prostrata	Running Postman	18	14cm pot	.1m x .6m
	·	•	18 50	14cm pot 14cm pot	.1m x .6m .2m x .7m
KP	Kennedia prostrata	Running Postman		·	
KP MYN	Kennedia prostrata Myoporum parrifolium ' Yareena'	Running Postman Creeping Boobialla	50	14cm pot	.2m x .7m
KP MYN MYP PAT	Kennedia prostrata Myoporum parrifolium ' Yareena' Myoporum parrifolium	Running Postman Creeping Boobialla Creeping Boobialla Pachysandra	50 15	14cm pot	.2m x .7m .2m x 1m
KP MYN MYP PAT	Kennedia prostrata Myoporum parrifolium 'Yareena' Myoporum parrifolium Pachysandra terminalis	Running Postman Creeping Boobialla Creeping Boobialla Pachysandra	50 15	14cm pot	.2m x .7m .2m x 1m
KP MYN MYP PAT TUSSOO	Kennedia prostrata Myoporum parrifolium ' Yareena' Myoporum parrifolium Pachysandra terminalis EKS / GRASSES / EVERGREEN PERENI	Running Postman Creeping Boobialla Creeping Boobialla Pachysandra	50 15 24	14cm pot 14cm pot 14cm pot	.2m x .7m .2m x 1m .2m x .7m
KP MYN MYP PAT TUSSOC DR FG	Kennedia prostrata Myoporum parrifolium ' Yareena' Myoporum parrifolium Pachysandra terminalis CKS / GRASSES / EVERGREEN PERENI Dianella revoluta var. revoluta	Running Postman Creeping Boobialla Creeping Boobialla Pachysandra NIALS Black-Anther Flax-Lily	50 15 24	14cm pot 14cm pot 14cm pot	.2m x .7m .2m x 1m .2m x .7m
KP MYN MYP PAT TUSSOC	Kennedia prostrata Myoporum parrifolium ' Yareena' Myoporum parrifolium Pachysandra terminalis EKS / GRASSES / EVERGREEN PERENI Dianella revoluta var. revoluta Festuca glauca	Running Postman Creeping Boobialla Creeping Boobialla Pachysandra NIALS Black-Anther Flax-Lily Blue Fescue	50 15 24 7 11	14cm pot 14cm pot 14cm pot 14cm pot 14cm pot	.2m x .7m .2m x 1m .2m x .7m



PROPOSED CHILDCARE CENTER 24-26 HONEYEATER WAY PAKENHAM PROJECT NO. # L9663 SHEET SIZE DESIGNED BY: N.H/MA landscape Arch. UEL/UK DRAWN BY: A.S Keystone Alliance Pty Ltd 277 Plenty Road, Preston VIC 3072 E: nina@keystonealliance.com.au

W: keystonealliance.com.au



Specifications

Site preparation to be carried out in accordance with best horticultural practice and under suitable conditions. Disturbance to indigenous soil structure is to be minimised. The use of machinery that may damage soil structure or profile is not acceptable. Sub-grade to all lawn and planted areas is to be cultivated to a minimum depth of 150mm and shaped to achieve drainage falls prior to topsoiling. Subgrade to be tested prior to preparation and conditioning to determine ph, salinity and gypsum requirement. Any gypsum required is to to be distributed at the manufacturers recommended rate and cultivated into the sub-grade at a minimum depth of

150mm . Proposed topping areas to be graded / drained to prevent water discharge into

This copied document is made available for the purpose of the planning process

neighbouring properties

Remove and dispose of environmental weeds off site prior to subgrade preparation, topsoiling and planting works.

Topsoil is to be spread in maximum 150mm layers, lightly compacted by use of a 150 - 200kg roller, or by thoroughly walking until it accords with finished kerb levels or to within 75mm below edging levels to accommodate mulch. Imported topsoil for garden beds is to be medium texture general purpose garden soil and lightly compacted to minimum 300mm depth to garden beds. Soil is to comply with s.a.a. 2223-1978, and as follows:

free from perennial weeds and their roots, bulbs and rhizomes free from building rubble and any other matter deleterious to plant growth ph to be 6.0 - 7.0

texture to be light to medium friable loam

Imported topsoil for lawn rejuvenation / establishment shall have the above characteristics, but shall be a free draining sandy loam lightly compacted to minimum 100mm depth

The specified mulch for garden beds is to be an aged organic material with 60 - 80 percent of its volume being wood chips particles in a size range of 25 - 50 mm maximum. Mulch is to be spread at a consolidated depth of 75mm

If soil to planting hole is dry - fill with water and allow to drain completely. Tree roots are to be teased outwards if matted or circling occurs prior to backfilling. Place tree in centre of hole on firm soil to prevent sinking, ensuring top of the rootball is flush with the surrounding soil surface and the trunk is vertical. Backfill material is to be in a loose, friable state, with no bricks, rocks or foreign material - if sufficient material is not available form the original hole to backfill, a similar soil type must be sourced and used. Soil material must be firmly backfilled in layers to prevent large air pockets from occurring, then thoroughly watered in. Trees to be staked with two 2250mm x 70mm hardwood stakes driven firmly into the ground - stakes must not be placed through the rootball area. Trees are to be secured to each stake with a strong, soft and flexible material, tight enough to support the tree in windy conditions - yet loose enough to stimulate development of a good supportive root system. Tree tie material must not injure tree bark or restrict trunk growth for a minimum period of three years. Slow release fertiliser (3/6 month formulation) such as 'Osmocote' is to be applied to the top of the rootball area away from the trunk / stem to manufacturers specifications and watered in immediately. All trees to be mulched to a diameter of 1200mm wide and to a depth of 100mm but must not be in contact with the tree trunk. Mulch is to be an aged organic material with 60 - 80 percent of its volume being wood chip particles in a size range of 25 - 50mm maximum. Mulch is to be spread at a consolidated depth of 75mm. The planting hole surface is to be shaped to minimise waterlogging/excessive water retention but retain the mulch material neatly. The site must be left in a clean and safe condition

Plant Establishment Period

The landscape is to be maintained by applying best horticultural practice to promote healthy plant performance for a 13 week establishment period following the approval of Practical Completion by the responsible authority including (but not limited to) the following tasks -Pruning as necessary to maintain plants in a healthy and structurally sound manner, pest and diseases - vegetation to be pest and disease free, mulching, staking and tying - 75mm mulch depth to be maintained around tree bases throughout maintenance period, watering - as often as necessary to ensure healthy and vigorous growth in accordance with current local watering regulations, weeding - maintained in a weed free state over the entire mulch area by spraying or mechanical mean, fertilising - 3/6 x monthly slow release fertiliser in accordance with manufacturers recommended application rates, replacement of deceased, stolen or vandalised plants beyond repair or regrowth with the same species as specified in the plant schedule within the assigned maintenance period

An in-ground automatic drip irrigation system to be installed to all garden areas and planter boxes (If applicable) in accordance with current local watering regulations

Timber edging to be 75mm x 25mm treated pine secured to 300mm long treated pine stakes at

nom. min 1000mm spacings with galvanised screws and installed to all junctions between garden beds, lawn and topping / pebble areas

Landscape and / or building contractor(s) are responsible for civil and hydraulic computations for landscape building works including, but not limited to surface and sub surface drainage for all

landscape areas prior to commencement of works While care has been taken to select tree species with non-invasive root systems it is recommended that root control barriers be installed for any trees located within two metres of

any building lines. Climbing plants (If applicable) are to be trained to supportive mesh, wire or lattice fixed over entire fence section from base to top

Do not scale from plan - contractor to verify all dimensions on site prior to commencing construction

Plants - Quality of Trees and Shrubs

Trees and shrubs shall be healthy nursery stock free from insects, diseases and weeds. The specified plant heights, and pot sizes are minimums. if plant material is unavailable in these sizes, larger stock must be used. Plant substitution is not acceptable unless confirmed by the responsible authority in writing. The contractor is to supply and install semi mature trees which meet the following criteria: Have a minimum planted height to sizes as indicated in the plant schedule, have a minimum trunk calliper of 50mm at ground level, be undamaged and free of diseases and insect pests, not be root bound or have circling or girdling roots but have roots grown to the edge of - the container, should bear a single straight trunk, strong branching pattern, and full canopy, show healthy, vigorous growth

Protection of Existing Trees

All existing vegetation shown on the endorsed plan (subject site and neighbouring properties) to be retained must be suitably marked before any development (including demolition) commences on the land and that vegetation must not be removed, destroyed or lopped without the written consent of the responsible authority. Before the commencement of works (including demolition) start, tree protection barriers must be erected around trees (subject site and neighbouring properties) to form a defined tree protection zone during demolition and construction in accordance with tree protection measures as per AS 4970-2009 (Tree protection in development sites).

Any pruning that is required must be carried out by a trained and competent arborist with a thorough knowledge of tree physiology and pruning methods to carry out pruning to the Australian standard - AS 4373-2007 (Pruning of amenity trees). All tree protection practices must be in accordance with a consulting arborist and / or to the satisfaction of the responsible

Proposed pathway

Fences with heights and material as nominated